

General Contractor's Guide to Mass Timber Project Estimation

Presented by Jeff Chan,
Seagate Mass Timber
and Steve Whitcraft,
Turner Construction Company

August 12, 2022



Photo: INTRO Cleveland / Hartshorne Plunkard Architecture / photo WoodWorks

Resources

CASE STUDIES

Adidas East Village Expansion

Innovative mass timber designs meet ambitious construction timeline



Nez Perce-Clearwater National Forests Supervisor's Office

Mass timber project yields low profile exterior, spacious interior.



CAD/Revit tools

Free downloadable details in PDF, DWG, or Revit formats
www.woodworks.org/cad-revit/mass-timber/

Visit woodworks.org/learn/

Upcoming Events

Common Challenges in Light Wood-Frame Gravity Structural Design | September 15

1.0 AIA/CES HSW LUs, 1.0 PDH credit, 0.10 ICC credit

Visit woodworks.org/events





**WOOD
PRODUCTS
COUNCIL™**



September 12-14
Boston, MA

Proud to Partner With

**Building the Playbook for the Future of
Taller, More Innovative Timber Structures**

www.advancing-mass-timber.com

Mass Timber Business Case Studies

Real financial information on real deals

- Prepared by WoodWorks and Conrad Investment Management
- Include qualitative influences + quantitative data to examine investment success

PROPERTY SUB-TYPES:

For-Rent Institutional Housing • Institutional Offices •
Industrial Buildings • Redevelopment/Additions •
Purpose-Built Owner/Occupied (Student Housing)



« Scan the code to download the current package.



New for GCs and installers: U.S. Mass Timber Construction Manual



PHOTO: MARCUS KAUFFMAN

U.S.
Mass Timber
Construction
Manual



Download free at
woodworks.org



Nominations Open

| Visit woodworks.org/nominate

2023 Wood Design Awards

| DEADLINE: OCT. 14, 2022



The Lighthouse | Gensler
Photo Jason O'Rear

Design Professionals: One-on-One Support & Assistance

PROJECT SUPPORT FIELD DIVISION

Senior Director
Field Division West



Janelle Leafblad, PE

OPEN POSITION

COMING SOON



David Hanley

OPEN POSITION



Anthony Harvey, PE



Marc Rivard, PE, SE

Senior Director
Field Division East



Jason Reynolds, MBA, DBIA



Chelsea Drenick, SE



Mike Romanowski, SE



Momo Sun, PE, PEng



John O'Donald II, PE



Mark Bartlett, PE



Jason Bahr, PE



Laura Cullen, EIT



Jessica Scarlett



Jeff Peters, PE, CGC

Find the Regional
Director for your
location:



Meet the Help Desk



Scott Breneman, PhD, PE, SE



Ashley Cagle, PE, SE



Karen Gesa, PE



Bruce Lindsey



Melissa Kroskey, AIA, SE



Terry Malone, PE, SE



Ricky McLain, PE, SE

Need technical assistance on a project?

Email: help@woodworks.org

NOW HIRING

TECHNICAL DIRECTOR,
US REMOTE

AND


REGIONAL DIRECTOR
BASED IN SEATTLE



visit woodworks.org/careers

Current State of Mass Timber Projects

As of June 2022, in the US, **1,502** multi-family, commercial, or institutional projects have been constructed with, or are in design with, mass timber.



Source: WoodWorks, June 30, 2022

* This total includes modern mass timber and post-and-beam structures built since 2013

Scan this code or use the url to find the map and more details online.



<https://www.woodworks.org/resources/u-s-mass-timber-projects/>



Continuing Education Credits

- Participants will receive a certificate of completion via email
- AIA credits will be processed by WoodWorks


Go to woodworks.org/webinar

1. To download the group sign in form
2. To download the presentation pdf

Ask Questions through the Q&A Box



- » Submit questions in the **Q&A** box at the bottom of your screen as they come up in the presentations. We will get to as many questions as possible.



“The Wood Products Council” is a Registered Provider with The American Institute of Architects Continuing Education Systems (AIA/CES), Provider #G516.

Credit(s) earned on completion of this course will be reported to **AIA CES** for AIA members. Certificates of Completion for both AIA members and non-AIA members are available upon request.

This course is registered with **AIA CES** for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.

Questions related to specific materials, methods, and services will be addressed at the conclusion of this presentation.

Course Description

How can general contractors meet the growing demand for mass timber buildings? While developers across the country are pursuing mass timber projects, knowledge among the general contractor community is not yet widespread. Companies have varying degrees of familiarity with both the products and practicalities of estimating, sourcing, and building a modern mass timber structure, and early adopters continue to play a significant role in educating the rest of the community. This presentation seeks to build on this openness and environment of shared learning, providing an overview of mass timber estimation and bidding processes. We'll also discuss why some mass timber projects face resistance, and how to overcome value misconceptions to achieve success. With an emphasis on real projects, -these discussions will also include preconstruction coordination, BIM and Virtual Design and Construction, and incorporating MEPF subcontractors into a competitive bid.

Learning Objectives

1. Identify the value propositions that can inform a mass timber estimation process and translate into competitive bids.
2. Understand what drives estimating differences between general contractors and specialty installers.
3. Discuss perceived cost saving measures, the efficiencies gained or lost, and lessons identified from built projects.
4. Discuss estimates for project overhead, specifically cost analysis, BIM and VD&C requirements.



Mass Timber: *Commercial Considerations*

Estimating and Procurement

Steve Whitcraft, DBIA, AIA Assoc, CPC
Turner Construction Company



Disclaimer: This presentation was developed by a third party and is not funded by WoodWorks or the Softwood Lumber Board.

Outline

1. Motivation and Commitment of Owner
2. Basic Mass Timber Components
3. Early Decisions
4. Procurement Strategies
5. Comparison to Other Structural Systems
6. Summary Take-Aways
7. Questions

Owner Motivation/Commitment

1. What is Driving Owner to Consider MT?

ESG – Doing the Right Thing

Improved Employee/Tenant Environment
(Amenity)

Cost (First vs LCA vs Sale)

2. What Stage of Commitment?

All-In Day One

Compare at Concept – SD

Bid at DD - CD

Common ESG Factors for REITs



Components

1. Wall & Floor Panels

CLT

Glulam Panels

NLT/DLT

LVL/LSL/MP Panels




Wall & Floor Panel Type Examples:

- NLT - Nail Laminated Timber
- GLT - Glued Laminated Timber
- CLT - Cross Laminated Timber
- DLT - Dowel Laminated Timber
- LSL - Laminated Strand Lumber
- LVL - Laminated Veneer Lumber
- TCC - Timber-Concrete Composites

2. Columns/Purlins/Beams

Glulam

- Various Sizes/Layups for Required Loads
- Shapes: Straight, Curved, or Cambered




Connections

- Typically Steel
- Various Types
- Often Encased in FRR Layer

Components

3. Connection Hardware/Fasteners



Job Name

Jobsite Photos

Column Connection

Misc. Connection Details

Floor Assembly




Early Decisions

1. Lateral System

Steel BRB Core

Concrete Core

Bracing Configuration



2. Floor Assembly ($C_f/B_f + Pcs$)

Diaphragm Connection

Lay-Up (Deck/Purlin/Beam config)

Grid Spacing



Early Decisions

3. MEP System Routing

Exposed/Covered/Through
Beams

UFAD/Radiant/Overhead
HVAC



4. Façade Attachment

Edge/Beam HDWE

Prefab Panels

5. Acoustic Performance



Early Decisions

6. Code Considerations

Type IA/Type III/Type 4A,B,C,HT

Future Tenant Flexibility

Local Changes/Adoption




TABLE 4: Select Height and Area Limits by Construction Type

		I-A	I-B	IV-A	IV-B	IV-C	IV-HT
Occupancies	Value	Allowable Building Height above Grade Plane, Feet (IBC Table 504.3)					
A, B, R	S	Unlimited	180	270	180	85	85
		Allowable Number of Stories above Grade Plane (IBC Table 504.4)					
A-2, A-3, A-4	S	Unlimited	12	18	12	6	4
B	S	Unlimited	12	18	12	9	6
R-2	S	Unlimited	12	18	12	8	5
		Allowable Area Factor (At), Feet ² (IBC Table 506.2)					
A-2, A-3, A-4	SM	Unlimited	Unlimited	135,000	90,000	56,250	45,000
B	SM	Unlimited	Unlimited	324,000	216,000	135,000	108,000
R-2	SM	Unlimited	Unlimited	184,500	123,000	76,875	61,500

S is sprinklered with NFPA 13 sprinklers. SM is the multi-story allowable area factor. Underlined entries are the new additions.

Fire-Resistance Rating Requirements for Building Elements (Hours)

Building Element	Type I		Type II		Type III		Type IV				Type V	
	A	B	A	B	A	B	HT	A	B	C	A	B
Primary structural frame ¹ (see Section 202)	3 ¹	2 ¹	1 ¹	0	1 ¹	0	HT	3	2	2	1 ¹	0
Bearing walls												
Exterior ¹	3	2	1	0	2	2	2	3	2	2	1	0
Interior	3 ¹	2 ¹	1	0	1	0	1/HT				1	0
Nonbearing walls and partitions	See Table 602											
Exterior												
Nonbearing walls and partitions	0	0	0	0	0	0	See Section 2304.11.2	0 ¹	0 ¹	0 ¹	0	0
Interior ¹												
Floor construction and associated secondary members (see Section 202)	2	2	1	0	1	0	HT	2	2	2	1	0
Roof construction and associated secondary members (see Section 202)	1-1/2 ¹	1 ¹	1 ¹	0 ¹	1 ¹	0	HT	1-1/2	1	1	1 ¹	0

¹Nonbearing interior wall partitions in Types IV-A, IV-B and IV-C must be of mass timber construction or of noncombustible materials per IBC 602.4

Source: IBC Table 601 / See IBC for footnotes

IBC 602.4 FRR comes from Mass Timber, added non-combustible protection or combination of both. IBC 703.5 and 722.7 give specifics.

Early Decisions

7. Sustainability Considerations

Adhesive/Sealer

Location/Transportation Sourcing
Options


Forest Certification
FSC/SFI/PEFC/CSA

Supply Chain Options – Forest to Mill
to Fabricator



Schedule Example

MASS TIMBER – CONCEPT THROUGH COMPLETION



Procurement Strategies

1. CM Turn-Key

Vendor Design/Fab/Erect

Vendor Design-Assist/Fab/Erect

2. GC Parts & Pieces

Vendor Fab

Vendor Erect

3. GC Self-Erect

Vendor Fab

Procurement Process



1 PRE-QUALIFY BIDDERS

Evaluation Criteria:

- Safety Record
- Past Performance Record
- References
- Current Work Load
- Financial Strength
- ISNet

2 COMPETITIVELY BID WORK

- Assemble bid packages, bid documents, and supplemental instructions for issuance.
- Conduct a pre-bid conference with specific trades to ensure conformance with drawings and sufficient bid coverage.

3 REVIEW BIDS

- All bids will be received and opened using procedures agreed upon by the team
- Once evaluated, bids will be recorded and documented on the master bid form.

4 BID ANALYSIS


- Once the bids are leveled, a final GMA will be prepared for review and approval.

5 AWARD OF CONTRACTS

- Upon approval of the final GMA, bids will be awarded in a timely manner in order to maintain an aggressive schedule.



Procurement Strategies



4. Important Considerations

Staging/Offloading

Factory vs Field-Installed Hardware

Factory vs Field-Applied Sealer

Moisture Mgmt. Factory to Occupancy

Safety Rails

BIM Coord/Penetrations – Sign-Offs

Field Conditions/Touch-Up



Structural System Comparison

1. Concrete/Steel vs Mass Timber

Separate Designs

Conceptual Deduct/Add

Trade Input

Fire Code/Building Type/AHJ/Design

Owner Priorities (First Cost/Other)

Decision Matrix

Structure Comparison - Concrete to Mass Timber			
April 7, 2022			
Concrete		Mass Timber	
Concrete Structure (2 thru roof)	23,195,825	Mass Timber Structure (2 thru roof)	20,900,000
Concrete Substructure (P1/P2/Lvl1)	17,018,934	Concrete Substructure (P1/P2/Lvl1)	16,869,074
		Concrete Topping (2 thru roof)	2,189,063
Steel (Pit/Screen/Misc)	1,642,052	Steel (BRB/Columns)	5,896,494
		Pile Reduction	(314,242)
		Structural Excavation Reduction	(98,995)
		General Conditions Reduction	(991,935)
Total			
Delta			
Material			
Total Material			
Total Fiber Quantity (CuFt)			
CLT			
Glulam			
Addendum 1 (2nd level Bridge)			
Bridge included			
Cross Laminated Timber (CLT)			
7-ply (alternate 9 5/8 equiv)			
9-ply (alternate 12 1/2 equiv)			
Strength Grade			
Surface Finish			
Spline Material			
Glulam Columns			
Strength Grade			
Glulam Beams/Furlins			
Length			
Strength Grade			
Hardware/Plates/Gussets for Mass Timb			
Fasteners			
Plates/Gussets/Column Bases			
Lifting Devices			
Lifting Devices/Misc			
Sealer			
Sealer			
Protective Wrap for Transport			
Transportation & Delivery to Jobsite			
Total Trucks/Trips			
Design Assistance (Total)			
Registered Professional Engineer			
BIM Coordination			
Participation in Meetings			
Fabrication Facility			
Location			
Time at location			
Capacity			
Lumber/Fiber Source (Control)			
Species CLT (SPF/DougFir, etc)			
Species Glulam (SPF/DougFir, etc)			
Fabrication Schedule			
Sign-off to start shipping			
First Delivery			
Exchange Rate			
Exchange Rate			
Erection			
Total Erection (\$)			
Total Erection (hrs)			
Crew makeup			
Production rate			
Field Erection Duration			
Touch-up			
Sanding/Resealing			
Misc Supplemental Items			
Install Splines			
F&I Seam Tape at Splines & Butt Joints			
Temporary Bracing			
F&I Seam Temporary Safety Rails			
Rigger/Rig Mat. (Spreader Bars, Slings)			
Tools, Equipment, & Aerial Lifts			
Total Base Proposal			
Alternates (Voluntary)			
Alternate FSC Certified			
Alternate Weather Membrane			

Structural System Comparison

2. Mass Timber Hybrid Solutions

Precast Beams/Columns – MT Decks


Concrete Cores/Shfts – MT Decks

BRB Shear – MT Decks

Other Combos (Delta Beam)

Relative Impacts to Other Trades

Tradeoff Pure MT for Cost Savings



Structural System Comparison

3. Additional Comparative Considerations


Foundation (Footing/Wall Sizing) Reduction

UFAD vs Exposed vs Topping vs Structural Diaphragm (Nail/Rebar/HBV)

MEP Exposed vs Traditional Ceilings (Owner Aesthetic)

Building Type Impacts/Restrictions (Type 1A vs III vs 4B/C vs 5)


Finishes Reduction (C/S and TI)



Benchmark Interiors Costs

OFFICE TENANT IMPROVEMENT COST GUIDE

PROJECT & DEVELOPMENT SERVICES
NORTH AMERICA 2021



Benchmark Interiors Costs

OFFICE TENANT IMPROVEMENT COST GUIDE

PROJECT & DEVELOPMENT SERVICES
NORTH AMERICA 2021

Dallas "First
Generation"
Space Cost (p. 18)



	1st Generation	Mass Timber Savings
General Requirements	\$1.13	
Demo Existing	\$1.00	
Final Cleaning	\$0.25	
Architectural Woodwork	\$3.37	\$0.62
Thermal Insulation	\$0.53	
Openings	\$3.24	
Glazing	\$3.31	
Metal Stud Framed Partitions	\$10.05	\$1.30
Tiling	\$0.31	
Acoustical Ceilings	\$3.14	\$2.14
Resilient Flooring	\$0.40	
Carpeting	\$3.70	
Painting	\$3.05	\$1.55
Signage	\$0.42	
Fire Extinguishers	\$0.13	
Appliances	\$0.48	
Window Shades	\$1.43	
Fire Protection	\$2.47	
Domestic Water Piping	\$0.62	
HVAC	\$11.54	
Electrical	\$13.59	
Subtotal	\$64.16	\$5.61
General Conditions	\$4.20	
GL Insurance	\$1.05	
GL Contingency		
GC Fee	\$2.21	
Total	\$71.62	\$5.61
Sales Tax Total		
Contingency (10% of Total)	\$7.16	\$0.56
Total with Tax and Contingency	\$78.78	\$6.17*

*1st Generation Tenant Space Cost Reduced by \$6.17

Potential
Reductions in TI
Cost Using Mass
Timber – ROM
\$6.17/sf

Lessons/Good Practices

1. Exchange Rates and Material Pricing (*tie to Index/Allowance*)

2. Moisture Management Plan – *Wrap/Seal/Touch-Up*

Splines/Tape for Spline Joints

3. Transportation/Unload-Staging - *JIT Efficiency*

4. Hardware/Fasteners/Plates/Bracing (*Weight/Who Designs*)

5. Lay-up Combinations (*Fabricator Standards & Erector Efficiency*)

6. Target Fiber Density (*BF/SF or CF/SF*) - Potential Cost/Design Optimization

7. Erection Production Goals (*% of Material or Pieces/Day*) - Potential Cost/Design Optimization

Summary Take-Aways

1. Choose a Reliable, Experienced GC/CM
2. Establish Priorities/Goals with Owner & Design Team
3. Determine Appropriate Procurement Strategy
4. Confirm Comparison/Determine MT Early
5. Bring In MT Team As Soon As Reasonable
6. Coordinate MT Details with Overall Design
7. Watch for Key Considerations
8. Learn from Trade Partners



MASS TIMBER PROJECT ESTIMATION

Presented by: Jeff Chan
Pre-Construction Manager



Disclaimer: This presentation was developed by a third party and is not funded by WoodWorks or the Softwood Lumber Board.

LEARNING OBJECTIVES



- Identify Unique Factors of Mass Timber Projects
- Account for the Complete Scope, Comparing Apples to Apples
- Mitigating Risk

MAIN PRICING COMPONENTS OF A SCOPE



- Supply
- Install
- Other Cost Considerations
- Design Assist & Value Engineering

** Important to consider how you want to structure the contract for the mass timber scope*

SUPPLY



- Understanding and Defining the Supply Scope
- Options for Supply Packages
- Understanding your suppliers / options
- Fabrication
- Logistics and Timelines
- Understanding Risks

DEFINING THE SUPPLY SCOPE



- **Type of Mass Timber Build**
 - Post & Panel
 - Post Beam & Panel
 - Hybrid
- **Related Scope Items**
 - Drag Struts, L-angle, Embeds
- **Coatings and/or Membranes**
- **Components**
 - Glulam
 - CLT
 - GLT
 - DLT
 - Steel Columns
 - Connections
 - Hardware

OPTIONS FOR SUPPLY PACKAGE



- **Single Source Supply**
- **Multiple Timber Suppliers**
 - Procure Glulam and CLT separately
- **Separate Steel Supplier for connections**
 - Would require offsite or onsite pre-assembly by installer


** Ultimately depends on comfort level of GC to manage scope*

SUPPLIER CONSIDERATIONS



- **North American & European**
- **Capabilities & Availability**
 - Products & Sizes
 - Wood Species
 - Capacity
 - Certification
- **3D Modeling & Value Engineering**
- **Pricing Factors**
 - Lumber Procurement & Availability
 - Pricing Stability

FABRICATION



- 3D Modeling & MEP Coordination
- Shop Drawings
- Manufacturing
- Machining
- Pre-Assembly requirement
- Coatings & Membranes

SUPPLY DELIVERY & SCHEDULE



- **Freight & Shipping**

- Offsite Storage / Staging
- Duty & Taxes
- Logistics



- **Schedule & Timelines**

- Shop Drawings
- Fabrication
- Shipping

UNDERSTANDING RISKS




- **Pricing Stability**
- **Capacity and availability of Supplier**
- **Lead times** (from design assist phase if required through to delivery to site)
- **Logistics & Shipping**
 - Shipping from Europe
- **Missing Cost Factors**
- **Trade Coordination**
 - MEP Penetrations

INSTALL



- **Defining your Scope**
- **Site Logistics**
- **Pre-Assembly Requirements**
- **Crane & Equipment**
- **Scheduling & Manpower**
- **Additional Cost Considerations**
- **Additional Miscellaneous Items**
- **Understanding Risks**

IDENTIFYING & DEFINING THE INSTALL SCOPE



- **Installation of Mass Timber Components**
- **Connection between Timber & Other Structural Components**
- **Related Scope Items**
 - Embeds
 - Perimeter Angles
 - Drag Struts
 - Ledgers
 - Brace Frames
- **Guardrails (# of Floors)**
- **Temporary Bracing**

SITE LOGISTICS



- **Sequencing & Conditions**
 - Truck Routes
 - Pick points & Strategy
 - Laydown & Storage Area
 - Site Conditions
 - Crane Location

PRE-ASSEMBLY REQUIREMENTS



- **Pre-Assembly Offsite**
 - Facility & Storage Requirements
 - Trucking & Shipping Logistics
- **Pre-Assembly Onsite**
 - Designated Onsite Location or Active Deck
- **Additional Time Requirements & Schedule Impact**
- **Equipment & Staging Requirements**

CRANE & EQUIPMENT



- **Hoisting /Crane**
 - Time allocation / Accessibility
 - Other hoisting methods
 - Crane Location, Reach & Capacity
- **Other Equipment**
 - Aerial equipment
 - Telehandlers

SCHEDULING & MANPOWER REQUIREMENTS



- **Schedule & Sequencing**
- **Strategic planning**
 - Mobilization
 - Itemize Scope
 - Establish Sequencing & Productivity
 - Driven by Crane and Pick Times
 - Allocate Manpower & Durations

SCHEDULING & MANPOWER REQUIREMENTS



- Number of Mobilizations
- Travel Costs & Live Out Allowance
- Labor Requirements

ADDITIONAL COST CONSIDERATIONS



- **Moisture Management Plan**
 - Mitigating Damage during Storage & Handling
 - What is the Final Finish
 - Weather & Building Conditions
- **Material Protection, Damage & Repairs**
 - Defining Scope & Responsibilities
 - Allocating Time
 - Cost

ADDITIONAL MISCELLANEOUS ITEMS




- **Lifting & Bracing Engineering Plan**
- **Fall Protection Plan**
- **Layout & Surveying**
- **Welding**
- **Regulatory Requirements**
 - City/County/State/Country Requirements

UNDERSTANDING RISKS




- **Crane Schedule and Allocation**
- **Scope Gaps**
- **Connection Details & Interaction with Trades**
- **Tolerances and Mitigating Re-Work**
- **Coordination between Supplier and Installer (if separated)**

CASE STUDY SCENARIO



- **5 Storey Mass Timber Office with Concrete Core**
 - 91,000 SF GFA (approx. 16,000 SF per Floor)
 - Post, Beam & Panel
 - Half Lap CLT Joints
- **Invited to Provide Turnkey Supply and Install Proposal and Install Only**
 - Hard bid to multiple GCs
 - Different GCs had their own approach

CASE STUDY SCENARIO



- **Supply Scope**

- Mass Timber Components (Glulam & CLT)
- Timber Connections
- Steel (Diaphragm Straps, Drag Plates, Perimeter Channel and CLT Bearing Ledgers @ Concrete Core)
- Timber Fasteners
- Shop Applied Membrane for Moisture Protection
- Shop Applied Sealers for CLT & Glulam
- Delegated Connection Design

CASE STUDY SCENARIO



Project Considerations

- **Supplier**
 - Looked at Options for Separating Scopes
 - Pre-assembly & Fabrication
 - Sourcing Locally
 - Certification & FSC
- **Design Assist & Value Engineering**
- **Modeling Capabilities**
- **Half Lap Instead of Splines (Lots of Diaphragm Steel)**
- **Use detailed "Supplier Bid Breakdown" to Align Scopes for all Bidders**

CASE STUDY - SUPPLY

MASS TIMBER SUPPLY				
Supplier				
ITEM OF WORK	Project Requirement	Included 04-Jul-22 Proposal	Excluded	Notes/Comments
Glulam Columns		\$ 144,000.00	\$ 0.00	
Supply	Supply	144,000.00		
Install	Install			
Finish	Finish			
Paint	Paint			
Seal	Seal			
Protective	Protective			
Glulam Beams		\$ 9,480,000.00		
Supply	Supply	9,480,000.00		
Install	Install			
Finish	Finish			
Paint	Paint			
Seal	Seal			
Protective	Protective			
CLT Panels		\$ 4,440,000.00		
Supply	Supply	4,440,000.00		
Install	Install			
Finish	Finish			
Paint	Paint			
Seal	Seal			
Protective	Protective			
Glulam Hardware		\$ 4,000,000.00		
Supply	Supply	4,000,000.00		
Install	Install			
Finish	Finish			
Paint	Paint			
Seal	Seal			
Protective	Protective			
CLT Hardware		\$ 4,000,000.00		
Supply	Supply	4,000,000.00		
Install	Install			
Finish	Finish			
Paint	Paint			
Seal	Seal			
Protective	Protective			
Additional Items		\$ 4,000,000.00		
Supply	Supply	4,000,000.00		
Install	Install			
Finish	Finish			
Paint	Paint			
Seal	Seal			
Protective	Protective			
Freight		\$ 4,000,000.00		
Supply	Supply	4,000,000.00		
Install	Install			
Finish	Finish			
Paint	Paint			
Seal	Seal			
Protective	Protective			
Design Engineering		\$ 4,000,000.00		
Supply	Supply	4,000,000.00		
Install	Install			
Finish	Finish			
Paint	Paint			
Seal	Seal			
Protective	Protective			
Schedule		\$ 4,000,000.00		
Supply	Supply	4,000,000.00		
Install	Install			
Finish	Finish			
Paint	Paint			
Seal	Seal			
Protective	Protective			

Develop a "Supplier Bid Breakdown" at an early stage:

- Lay out all Project Requirements
- Eliminates any Scope Gaps
- Speak with Suppliers early

CASE STUDY - SUPPLY

ITEM OF WORK	Project Requirer	Supplier 1 04-Jul-22	Comments	Supplier 2 06-Jul-22	Comments	Supplier 3 06-Jul-22	Comments	Supplier 4 03-Jul-22	Comments
Glulam Columns									
Specifier		B	000,000.00	B	000,000.00	B	000,000.00	B	000,000.00
Strength Grade		E1281		E1281		E1281		E1281	
Visual Grade		B10-B10		B10-B10		B10-B10		B10-B10	
Coating									
Finger		473		473		473		473	
Volume		749.3 CM		749.3 CM		749.3 CM		749.3 CM	
Certification		F81C		F81C		F81C		F81C	
Glulam Beams									
Specifier		B	0,000,000.00	B	0,000,000.00	B	0,000,000.00	B	0,000,000.00
Strength Grade		E1281		E1281		E1281		E1281	
Visual Grade		B10-B10		B10-B10		B10-B10		B10-B10	
Coating									
Finger		1853		1853		1853		1853	
Volume		3,383.5 CM		3,383.5 CM		3,383.5 CM		3,383.5 CM	
Certification		F81C		F81C		F81C		F81C	
CLT Panels									
Specifier		B	0,000,000.00	B	0,000,000.00	B	0,000,000.00	B	0,000,000.00
Strength Grade									
Visual Grade		B10-B10		B10-B10		B10-B10		B10-B10	
Coating									
Finger									
Volume		4728.5 CM		4728.5 CM		4728.5 CM		4728.5 CM	
Certification		F81C		F81C		F81C		F81C	
Glulam Hardware									
All Fabrication		B	0,000,000.00	B	0,000,000.00	B	0,000,000.00	B	0,000,000.00
Timber to Timber connections									
Preinstall		B	000,000.00	B	000,000.00	B	000,000.00	B	000,000.00
Timber to Concrete Connections									
Preinstall									
Reinforcing Screws (if needed)									
Wood Filler/Flux/Blockin									
All Fasteners									
Through Bolt/Pin/Rod/Nut/Washer									
Finish on Hardware Steel									
CLT Hardware									
Spline		B	0,000.00	B	0,000.00	B	0,000.00	B	0,000.00
All Fasteners									
Reinforcing Screws (if needed)									
Drag Plate									
Drag Plate Fasteners									
CLT Wood Lugs for 4"x4" Blocking									
Additional Items									
Shop Drawing									
3D Model									
Lifting Device Supply		B	000.00	B	000.00	B	000.00	B	000.00
Lifting Device Preinstall		B	0,000.00	B	0,000.00	B	0,000.00	B	0,000.00
Pre-Coordinate MEP Penetrations									
Freight									
Logistic Coordination		B	0,000,000.00	B	0,000,000.00	B	0,000,000.00	B	0,000,000.00
CLT Truck/Containers - Quantity			100		100		100		100
Glulam Truck/Containers - Quantity			100		100		100		100
Offload Time (trucking average rate budget)			21		21		21		21
Import Customs Fee									
Which Port									
Design Engineering									
Design Assist		B	0,000,000.00	B	0,000,000.00	B	0,000,000.00	B	0,000,000.00
Delegate Design of Connections									
Onsite Review?									
Onsite Review?									
Value Engineering									
Schedule									
Design Assist Period (Connection Design/ME)			20		20		20		20
Shop Drawing Period from Design Paid									
Shop Drawing Revision Turnaround Time									
Fabrication			18-19 weeks		18-19 weeks		18-19 weeks		18-19 weeks
Delivery			8-9 weeks		8-9 weeks		8-9 weeks		8-9 weeks
Contingency									
TOTAL			0000000000		0000000000		0000000000		0000000000

Bid Evaluation & Comparison


- Compare all Suppliers Once Each Supplier has been Assessed
- Add in any Risks or Contingencies

CASE STUDY - INSTALL



- **Install Scope**
 - Install Glulam Columns, Beams and CLT Floor/Roof Panels (Connections Pre-installed by Supplier)
 - Install Steel (Diaphragm Straps, Drag Plates, Perimeter Channel and CLT Bearing Ledgers @ Concrete Core, Perimeter HSS for Header and Sill Support)
 - Guardrails
- **Site Logistics**
 - Met with all bidding GCs to discuss their logistics
 - Site Conditions
 - # of Cranes & Placement (Tower Crane)
 - Schedule (Plan for Concrete Cores)
 - Review Scope
 - Truck Route
 - Possible Truck Staging Area

CASE STUDY - INSTALL



Scope Delineation

Project Considerations

- Larger crew to keep pace as there was a lot of steel to install
- Crane and site logistic for each GC
- Limited Onsite Storage Area
- Picks per day
- Material unloading strategy
- No allowances for onsite moisture management, material repairs or finishing

CASE STUDY - INSTALL

Scope Method

ITEM OF WORK	Quantity	Unit	Hours/Pc
Mobilize			
Project site setup	1	allow	
Layout	1	allow	
Surveying	1	allow	
Training/Orientation	240	pcs	
Mass Timber Installation			
Glulam Beams	224	pcs	
CLT Floor Panels	466	pcs	
Drag Strap	154	pcs	
102 x 102 x 9.5 HSS	30	pcs	
Fire Caulking per detail 6-A750	6	locations	
Perimeter C150x12 Channel	127	pcs	
1-53.00	142	pcs	
2-53.00	105	LF	
3-53.00	525	LF	
Fire Caulking per detail 5-A750	239	locations	
Demobilize	1	allow	
Allowances			
Warehouse/ Material Handling		months	
Adverse Weather Allowance		months	
Install Perimeter Guardrail	4	floors	
Overtime Allowance	12.5%		
Total			

- Scope Method is good for pricing as it covers all scopes
- Unit rates per item based on historical data
- Baseline of hours to complete the project and compare to sequence we develop
- Also incorporates project setup, mobilization and demobilization

CASE STUDY - INSTALL

Sequencing Method

Level	Mass Timber Pieces / Floor			CLT panel area (SF)	GFA (SF)	Perimeter (ft)
	Columns	Beams	Floor panels			
L1					20839	
L2	52	57	105	18,324	17825	845
L3	46	40	93	15,757	17793	610
L4	46	40	93	15,757	17793	610
L5	46	40	93	15,757	16770	610
Roof	46	40	93	15,757	0	
PH	4	4	6	823		
TOTAL	240	221	483	82,175	91,020	2,675

Task	QTY	Days	Workers
Stand L2-L3 columns	46	1.5	6
Place L2 glulam beams	40	1.5	6
Place L2 Panels	93	3	6
Splines/Steel/guardrails			4
Days Per Cycle		6	
# of Cycles		4	
Work Force	Rate	Units	
Crew Size	10	PPL	
Work Days / Week	5	Days	
Work Hours / Day	8	Hours	
Heaviest Item	9,200	LBS	
Typical Cycle Days	24	Day	
Additional Days	8	Day	
Mob/Demob	5	Day	
Layout	2	Day	
Sequencing Days	39	Day	
Weeks	7.8	Week	
Used Week	8	Week	
Total hours	3,120	Hours	
Productivity			
Hours/MSF	38.0	Hours/MSF	
SF/Week	10,272	SF	

- Sequencing Method is great for developing a schedule and optimizing the crane
- Develop a cycle based on the crane crew and staff up to complete non-critical tasks

CASE STUDY - REVIEW



Key Take Aways from Case Study

- GC's logistics plan and schedule can impact how we execute the mass timber scope
- Need to have very clear methodology to compare all bids received and allow contingencies for possible scope gaps
- Suppliers and installers may provide different bid packages based on their capabilities and willingness to take on scope items
- Understand if and how you want present cost savings measures if possible

ITEMS TO CONSIDER



- Allow for additional preconstruction and planning time compared to other construction methods
- Understand nuances between different mass timber players (suppliers, contractors, installers) and how they can affect pricing and risk
- Know your options and manage expectation
- Sequencing and trade coordination is key to driving schedule
- Strong communication between GC and mass timber proponents

LEARNING OBJECTIVES



- Identify Unique Factors of Mass Timber Projects
- Account for the Complete Scope, Comparing Apples to Apples
- Mitigating Risk

➤ QUESTIONS?

This concludes The American
Institute of Architects Continuing
Education Systems Course



Steve Whitcraft, DBIA, AIA Assoc, CPC

Turner Construction Company

swhitcraft@tcco.com



Jeff Chan

Seagate Structures (USA), Inc.

jchan@seagatemasstimber.com