

Timber Offices: Two Case Studies of Form, Function, and Sustainability

(AIA #19DS34 1.0 HSW; ICC #21375 0.1 ICC)



Stephen Guest AIA, LEED AP
RMW architecture & interiors



Marshall Andrews, LEED AP
DPR Construction



Disclaimer: This presentation was developed by a third party and is not funded by WoodWorks or the Softwood Lumber Board.

“The Wood Products Council” is a Registered Provider with The American Institute of Architects Continuing Education Systems (AIA/CES), Provider #G516.

Credit(s) earned on completion of this course will be reported to AIA CES for AIA members. Certificates of Completion for both AIA members and non-AIA members are available upon request.

This course is registered with AIA CES for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.

Questions related to specific materials, methods, and services will be addressed at the conclusion of this presentation.



Course Description

This presentation will showcase two modern wood office buildings in California—which are helping to lead a nationwide renaissance in creative wood design. First, the project architect for Ice Block 1, one of the first contemporary timber-framed midrise structures in Northern California, will share its story from the decision to use wood, through fire and seismic performance, to construction lessons learned and more. Second, the general contractor for the DPR office expansion in Sacramento will discuss unique aspects of a mass timber install over an existing structure. This project includes a 6,000-square-foot, glulam post-and-beam addition with CLT shear walls and roof framing over a structure built in the 1940s.

Learning Objectives

1. Review the design decisions that led to the use of wood on two recently completed office projects in California.
2. Discuss code-compliance design strategies for aspects such as fire and life safety and seismic lateral resistance.
3. Highlight how the use of timber allows for more sustainable construction and operation.
4. Explore the construction phase of a mass timber project, reviewing lessons learned, building official and inspector interaction, site safety and cost impacts.

ICE Block 1: Sacramento's First Mid-Rise Timber Office



R Street Historically was the Industrial Corridor for Sacramento



Served by rail



Business and industry flourished



Since the early 2000's the street has been a Special Planning district with many renovated historic warehouses


BACKGROUND

Project Began as a Renovation




The Crystal Ice factory served Sacramento from 1910 as the Principal supplier of block ice up until the 1970s as cold storage and then sat vacant until 2015

PROJECT SPECIFICS



4 Story building above 1 level of underground parking.



2 Level of poured in place concrete under 3 levels of timber framed wood.

PROJECT SPECIFICS




2 – 4 Story building wings shifted on site to allow for varied outdoor terrace depth connected by a bridge.

PROJECT SPECIFICS




2 – 4 Story building wings shifted on site to allow for varied outdoor terrace depth connected by a bridge.

PROJECT SPECIFICS



2 – 4 Story building wings shifted on site to allow for varied outdoor terrace depth connected by a bridge.

PROJECT SPECIFICS



2 – 4 Story building wings shifted on site to allow for varied outdoor terrace depth connected by a bridge.

PROJECT SPECIFICS


Raised ground floor pedestrian plaza to recreate loading dock aesthetic of traditional R Street.



DESIGN OBJECTIVES



Create authentic, historically referential architecture worthy of replacing the Crystal Ice renovation project.



Use mass timber


DESIGN OBJECTIVES

Natural Materials Palette



Timber, Raw Steel, Galvanized Industrial Panels, Clear Glass


DESIGN OBJECTIVES



The “big industrial shed” articulated structural frame with simple details.

PLANNING PROCESS

Research Precedents



PLANNING PROCESS

Market Analysis for Office/Retail Creative Space



MASS TIMBER GOALS



Maintain a historic frame look to be balanced - no deep girders shallow purlins, exposed connections

MASS TIMBER GOALS



Maintain a historic frame look to be balanced - no deep girders shallow purlins, exposed connections


MASS TIMBER GOALS



Develop an aesthetic to express the wood, both inside and out

MASS TIMBER GOALS


Validate the acoustics of exposed wood surfaces



CODE COMPLIANCE

4 Stories Plus Basement

Construction Type
Above: III-B
Below: I-A



Fully Sprinklered


Occupancy Groups
B / M / A-2 / S-2

CODE COMPLIANCE




Total area – 131,900 GSF above grade
Area per floor – 35,760 GSF

SEISMIC LATERAL RESISTANCE SYSTEM:



Buckling Restrained Braced Frame (6 per wing)
converts to shear walls at grade through parking garage

SEISMIC LATERAL RESISTANCE SYSTEM:



Buckling Restrained Braced Frame (6 per wing)
converts to shear walls at grade through parking garage

SEISMIC LATERAL RESISTANCE SYSTEM:



Buckling Restrained Braced Frame (6 per wing)
converts to shear walls at grade through parking garage

SEISMIC LATERAL RESISTANCE SYSTEM:



Buckling Restrained Braced Frame (6 per wing)
converts to shear walls at grade through parking garage

SEISMIC LATERAL RESISTANCE SYSTEM:



Buckling Restrained Braced Frame (6 per wing)
converts to shear walls at grade through parking garage

SEISMIC LATERAL RESISTANCE SYSTEM


Either in the plane of the frame line or outboard of the window wall with large steel drag plates through the curtain wall.

OSB diaphragm on all floors

Transfer girder at second floor



AESTHETIC CONSIDERATIONS




The Wood Aesthetic:
Grades, colors, connections, tolerances




AESTHETIC CONSIDERATIONS

Detailing to express the wood



AESTHETIC CONSIDERATIONS



Exposed utilities



AESTHETIC CONSIDERATIONS



Managing the tenant work letter


CONSTRUCTION CHALLENGES



Keeping the wood dry/protected




CONSTRUCTION CHALLENGES



Designing and specifying
concrete slabs over wood decks




CONSTRUCTION CHALLENGES



Moving and placing the wood
without damage

BUDGET



Total Project budget – 26.2 million for urban infill construction in 2016 California dollars –warm shell (non-union labor)

171,000 GSF = \$ 150.00/GSF
(Garage along was \$ 105/SF)

130,500 RSF = \$ 195.00/RSF

114,500 USF = \$ 222.00/USF

BUDGET

Comparison with 2020 Type III-A
warm shell
Mass timber – \$220.00
(no podium / no parking)



LESSONS LEARNED



Keep the wood dry

LESSONS LEARNED



Heavy timber is a carpenter's trade not a cabinetmaker's




LESSONS LEARNED



Select your Construction team wisely –
experience and enthusiasm for new paradigms

LESSONS LEARNED



Be vigilant for anchor/connection strategies that assume concealed construction

LESSONS LEARNED



The way we detailed this building was not conducive to fast construction


LESSONS LEARNED



Rated assemblies that engage the wood timbers are not often pretty



LESSONS LEARNED



Pay attention to the construction type transitions



LESSONS LEARNED

Clients will be in uncharted visual territory – MOCK STUFF UP



HOW DOES THE SPACE WORK?

“We love our new workplace in Ice Block I. Our former headquarters was in the Bay Area in a traditional office building. We all were out the door at 5:30 pm. In Ice Block, we want to stay in the office longer. I’ve heard architects wax over the years about how architecture can have an impact on how one feels. It wasn’t until we moved into Ice Block I that I understood this concept. We love the building and we love our new workplace, both designed by RMW.”

- Steve Eggert, Founder, Anton Dev Co.



HOW DOES THE SPACE WORK?



Anton

HOW DOES THE SPACE WORK?

“We renovated all of our showrooms (SF, San Jose and Sacramento) at the same time. Our SF and San Jose showrooms are located in traditional high-rise buildings. Our Sacramento showroom is our favorite because the architecture of Ice Block I gave us the framework to create the most interesting space.”

- Mark Dailey, President, KBM-Hogue Furniture



HOW DOES THE SPACE WORK?



KBM Hogue

HOW DOES THE SPACE WORK? /LEASING VELOCITY



Sky Lounge

Timber Offices: Two Case Studies of Form, Function, and Sustainability


(AIA #19DS34 1.0 HSW; ICC #21375 0.1 ICC)



Marshall Andrews, LEED AP
DPR Construction



Disclaimer: This presentation was developed by a third party and is not funded by WoodWorks or the Softwood Lumber Board.



1801 J

Project Goals

Goals, Certifications & Themes

■ DPR Sacramento

DPR's Point of View embodies two fundamental beliefs; Respect for the Individual and the belief that We Can Change the World. Our new office in Sacramento, which seeks to achieve LEED Platinum, Zero Net Energy and WELL Building Certifications, will create an environment that lives up to DPR's lofty goals.

Rather than building new, DPR chose to renovate the 26,872-sq.-ft. space, which was originally built in 1940. This decision emphasizes DPR's commitment to sustainability and to moving the industry forward, showcasing how older structure can be transformed into sustainable, highly desirable office space.

To be considered a success, the project must live up to the goals set from the beginning:

1. Taking Care of People & Place by providing a welcoming atmosphere for DPR and its customers, partners and surrounding communities built within an environmentally & socially conscious means.

2. Creating a Transformative Workplace that will challenge staff to think differently about work and provide flexibility for future growth.

3. Executing design & construction in a Fiscally Responsible manner that will analyze life cycle costs and be on par with comparable market rate developments.

4. Pursuing solutions that are Innovative & Simple to showcase what can be possible with commercially available products while maintaining DPR's passion to stand out from the crowd.

Targeted Certifications



LEED BD+C

Yes: 47 ????: 21 No: 44



LEED ID+C

Yes: 75 ????: 17 No: 17



WELL v2

Yes: 58 ????: 106 No: 10



ILFI ZNE

Production: 267,699kWh/yr (108%)



ILFI Petal Certification
Place | Energy | Beauty



Yes: 104.59 ????: 31.64 No: 7.33



DPR EUI: 27 | Tenant EUI: 30

Sustainable Features




- 1 Existing Trees** - Trees preserved, used for shading interior
- 2 Solar Tubes** - Tubular skylights were installed on the new and old roofs to maximize filtered daylight reducing reliance on artificial lighting.
- 3 Operable Windows with High-Performance Glazing** - all glazing in existing building replaced to high performance
- 4 Exterior Sun-Shading**
- 5 Vegetated Roof and shaded roof terrace** - A new rooftop terrace creates a parklike space for work or respite.
- 6 Retractable Wall/ Door**
- 7 Mass Timber Construction Addition** - This low-carbon, low-toxin material creates a sleek, serene environment and improves indoor air quality. First use of CLT shear walls in CA.
- 8 Adaptive Reuse of Existing Building** - A 1940s era building, once a vehicle testing facility, has been converted in a model of efficiency and community resilience.
- 9 Seed Wall**
- 10 Thermal Labyrinth** - Ventilation system conditions the building by drawing outdoor air through a concrete maze located in the existing basement. Through heat exchange with the ground, outdoor air is pre-cooled and pre-heated in the summer and winter seasons, respectively.

- 11 Red/Green Light Indicator Operable Windows**-indicator lights are controlled by the BMS and will leverage public data from the air quality sensors installed at California's Air Quality Board building which is located within 1 mile of the project.
- 12 New Communicating Stair** - to encourage active design/ connection to community
- 13 Lucid Dashboard** - DPR can view, compare and share energy and water use data in real-time. Staff can assess energy consumption rates and adjust practices, as required, encouraging employees to actively participate in maintaining the building's functionality.
- 14 Photovoltaics** -new photovoltaic panels were integrated in a typical locations—above the rooftop terrace, existing/ new roof and carport, offsetting all operational energy on an annual basis resulting in a net-positive energy facility
- 15 Rightsized & Flexible Workspace** - DPR's agile workspace reflects its family-like culture, rightsized to flexibly accommodate employees that spend more time at job sites than in the office and to encourage collaboration.
- 16 Biophilia** - From exposed woodgrain panels, to sculptural "grow columns," a seed wall, abundant plantings, and oversized sliding windows, the design creates a soothing environment that brings users closer to nature.
- 17 Certifications** - The project is targeting LEED Platinum (Interior) and Gold (Core+Shell) certification, WELL v2, REVEAL, fitwel, Energy Star, and ILFT's Zero-Net Energy certification.



CONNECTION TO SACRAMENTO COMMUNITY



CITY OF TREES



WATER



CROSS LAMINATED TIMBER - INTERIOR





Experience

Mass Timber Projects In Design and Constructed in the US (December 2018)



Stage

- Construction Started / Built
- In Design

Stage	Mass Timber	# of Projects
Construction Started / Built	CLT	16
	Heavy Timber Decking	3
	Post & Beam	7
	Total	26
In Design	CLT	24
	NLT	1
	Heavy Timber Decking	1
	Post & Beam	14
	Total	40
Grand Total		66

Construction Started / Built

State	City	Construction Started / Built			In Design			Grand Total
		CLT	Heavy Timber Decking	Post & Beam	CLT	Heavy Timber Decking	NLT	
CA	Angwin							1
	Bethel Island				1			1
	Brentwood	1						1
	Claremont			1				1
	Davis							1
	Dublin				1			1
	East Palo Alto	1						1
	Fourteen Valley				1			1
	Frasier Park	1						1
	Hayward				1			1
	Long Beach			1				1
	Los Angeles	1			2			3
	Madera				1			1
	Mendocino			1				1
	Merced				1			1
	Morgan Hill	1						1
	Mountain View	2						2
	National City						1	1
	Newport Beach	1						1
	Oakland	1		1		3		5
	Porterville					1		1
	Quincy	1						1
	Richmond							2
	Sacramento			1		1		2
	Selma			1				1
	San Diego	2						2
	San Francisco					6		6
	San Jose	1					1	2
	Santa Clara			1				1
	Santa Monica					1		1
Santa Rosa	1						1	
South San Francisco	2						2	
Sunnyvale					1		1	
Tahoe							1	
Truckee					2		2	
Universal City							1	
Walnut Creek			1				1	
West Sacramento							1	
Yuba Burea Island							1	
Total		10	3	7	24	1	1	14

Considering mass timber for a project?
Ask us anything.

For free project support, contact:
help@woodworks.org
woodworks.org/project-assistance

Mass Timber

Overview



Cross Laminated Timber (CLT)

Structural timber made up of pressed dried timber boards stacked at right angles and glued together with non-toxic adhesive



Glue Laminated Timber

Structural timber made up of layers of dimensioned lumber bonded together in a parallel orientation.

2nd

DPR Installation of CLT

9625 Towne Center Dr.

San Diego, CA

- Developer: Alexandria
- Occupant: Tekeda
- CLT Roof Deck
- 1st DPR CLT Installation
- DPR SPW crew had to re-plumbing new steel structure due to higher tolerances from CLT structure



9625 Towne Center

Lessons Learned

- Jurisdictional approval – CLT thickness, splice joints
- Detailing is the longest process
- Identify factory vs. field penetrations (MEP coordination)
- Tolerances of structural connections
- Acceptance of control samples (species, glues, finishes)
- Installation – staging, trucking, cabling of columns
- Temp waterproofing to avoid staining & mold
- SAFETY: Pre-installed perimeter guardrails

An architectural rendering of a modern building interior. The space features extensive wood paneling on the walls and ceiling, creating a warm, natural atmosphere. A prominent feature is a wide, light-colored wooden staircase with a dark metal handrail, leading from a lower level to an upper mezzanine. Large windows and glass railings provide views of the exterior and other levels. Several people are shown walking through the space, adding a sense of scale and activity. The lighting is soft and even, highlighting the textures of the wood and the clean lines of the architecture.

1801 J St.

Sacramento, CA

- 6,000sf 2nd floor expansion to existing building
- Type V-B Construction
- Glulam beams & columns
- CLT windwalls, shearwalls and roof deck
- Digitally pre-fabricated off-site in Penticton, BC Canada

1st

CLT Installation in Sacramento, CA


1st

CLT Shearwall Installation in California

#1

Largest Mass Timber Vertical Expansion to
an Existing Building in the US

Floorplans & Elevations



- OFFICE LEASABLE SPACE
- FOOD SERVICE LEASABLE SPACE
- RETAIL/FITNESS LEASABLE SPACE
- SHARED AMENITY
- DPR CIRCULATION
- DPR EXTERIOR AMENITY
- DPR OPEN COLLABORATION
- DPR COLLABORATION
- DPR FOCUS WORK
- TOILET ROOM
- DPR BACK OF HOUSE
- EXPRESS EXIT



Before & After



Before & After



Before & After







Code Approvals

March 14, 2019

Scott Hooker
President
Buehler Engineering, Inc.
600 Q Street Suite 200
Sacramento, CA 95811

Subject: 1801 J Street – California Mass Timber Competition

Dear Mr. Hooker,

We are writing a letter of support for Buehler's role in obtaining a building permit for a project using CLT construction at 1801 J Street.

Buehler and DPR met with the City on March 9, 2018 to present their CLT concept, gauge the City's openness to approving a project using CLT, and to determine the City's requirements to achieve approval. The City asked Buehler to prepare two Alternate Materials, Design and Methods of Construction requests per the California Building Code to address the use of CLT as elements of the primary Lateral Force Resisting System (LFRS): 1) utilization of CLT as the structural diaphragm for the East Building roof, and 2) utilization of CLT shearwalls at the second level of the new East Building.

The preliminary AMMR's were received March 28, 2018 and approved on August 31, 2018. Buehler was proactive and transparent throughout the AMMR approval process. They addressed the City's questions and concerns with research and calculations supporting the design. The project was submitted for plan review on May 18, 2018 and the permit was issued on September 10, 2018.

1801 J Street is Sacramento's only approved project using CLT for the both the diaphragm and lateral system. Utilizing CLT to retrofit and renovate the existing building satisfied the City's desire to conserve Sacramento's history while strengthening and modernizing the existing, unassuming office space.

Sincerely,

Anna Tekautz

Anna Tekautz, S.E.
Supervising Engineer

Alison Konwinski

Alison Konwinski, S.E.
Senior Engineer

SACRAMENTO
Community Development

Request for Alternate Materials, Design and Methods of Construction

Project location: 1801 J Street, Sacramento, CA
 Permitted or Activity Number: 1818-001
 Building Construction Type: 7
 Building Area (sq. ft.) and stories: 28,000 sq. ft. and two stories
 Building Occupancy Type: R40 (Office) - 4 office workers
 Fire Protection Systems Current (i.e. sprinklers/alarms): None and fire alarm

APPROVED
By: *Alison Konwinski*
on 04-15-2018

ISSUED BY
By: *Allyssa*
on 04-15-2018

For sections 7 through 17 provide a separate document that addresses each statement:
 8. Background for Alternate Methods Request:
 9. Code/Ordinance Requirements:
 10. Alternative Code Compliance:
 11. Staff Position (if applicable, check "Not Applicable" - STAFF USE ONLY)

Reviewed by: *Scott H. Hooker*
 Chief Building Official
 Signature & Date: 03/17/18

Approved by: *Mike Brumback*
 Fire Marshal
 Signature & Date: 03/17/18

STAFF (Please name and title): *Alison Konwinski, Senior Engineer*

Check one: APPROVAL RECOMMENDED NOT RECOMMENDED

Reviewed by: *Anna Tekautz, S.E.*
 Supervising Engineer
 Signature & Date: 03/17/18

Check one: APPROVAL RECOMMENDED NOT RECOMMENDED

Approved by: *Michael DeLuca, PE, CDO*
 Chief Building Official
 Signature & Date: 03/17/18

Approved by: *Jason Lee*
 Fire Marshal
 Signature & Date: 03/17/18

CHIEF BUILDING OFFICIAL: *Michael DeLuca, PE, CDO* FIRE MARSHAL: *Jason Lee*

ISSUED (check, if applicable) _____ ISSUED (check, if applicable) _____

This approval is specific to this project and this request, and is not transferable.

COM-1809305 & COM-1809314

SACRAMENTO
Community Development

Request for Alternate Materials, Design and Methods of Construction

Project location: 1801 J Street, Sacramento, CA
 Permitted or Activity Number: 1818-001
 Building Construction Type: 7
 Building Area (sq. ft.) and stories: 28,000 sq. ft. and two stories
 Building Occupancy Type: R40 (Office) - 4 office workers
 Fire Protection Systems Current (i.e. sprinklers/alarms): None and fire alarm

APPROVED
By: *Alison Konwinski*
on 04-15-2018

ISSUED BY
By: *Allyssa*
on 04-15-2018

For sections 7 through 17 provide a separate document that addresses each statement:
 8. Background for Alternate Methods Request:
 9. Code/Ordinance Requirements:
 10. Alternative Code Compliance:
 11. Staff Position (if applicable, check "Not Applicable" - STAFF USE ONLY)

Reviewed by: *Scott H. Hooker*
 Chief Building Official
 Signature & Date: 03/17/18

Approved by: *Mike Brumback*
 Fire Marshal
 Signature & Date: 03/17/18

STAFF (Please name and title): *Alison Konwinski, Senior Engineer*

Check one: APPROVAL RECOMMENDED NOT RECOMMENDED

Reviewed by: *Anna Tekautz, S.E.*
 Supervising Engineer
 Signature & Date: 03/17/18

Check one: APPROVAL RECOMMENDED NOT RECOMMENDED

Approved by: *Michael DeLuca, PE, CDO*
 Chief Building Official
 Signature & Date: 03/17/18

Approved by: *Jason Lee*
 Fire Marshal
 Signature & Date: 03/17/18

CHIEF BUILDING OFFICIAL: *Michael DeLuca, PE, CDO* FIRE MARSHAL: *Jason Lee*

ISSUED (check, if applicable) _____ ISSUED (check, if applicable) _____

This approval is specific to this project and this request, and is not transferable.

Sustainability

2,432

Cubic Feet of Wood Products
Used

12

Seconds for US & Canadian
Forest to Grow This Wood

55

Metric Tons of CO₂ Stored in
the Wood

115

Metric Tons of CO₂ Avoided in
Greenhouse Gas Emissions


14

Homes Per Year

33

Cars Off the Road Per Year

Mass Timber Logistics




New DPR Sacramento Office

Clash Coordination



New DPR Sacramento Office


BIM Detailing for Aesthetics





New DPR Sacramento Office

Mass Timber Logistics











B17 SLIDES SOUTH INTO HANGER (2/S5.4) ON C41 COLUMN @ 5/7.8


*NOTE: COLUMN & BEAM IDENTIFICATIONS SUBJECT TO CHANGE UNTIL IFC DRAWING SET. ABOVE SHOWN FOR SEQUENCE AND REFERENCE ONLY.




C31.1 WITH HANGER (2/S5.4) PRE-ATTACHED SLIDES SOUTH INTO B17 @ C/7.8




B6 SLIDES EAST INTO HANGER (2/S5.4) WHICH IS PRE-INSTALLED ON B17.
B13 SLIDES SOUTH INTO HANGER (2/S5.4) WHICH IS PRE-INSTALLED ON C41 @ A/7.5.




B18 IS RAISED VERTICALLY IN PLACE. KNIFE PLATE (6/S5.2) IS INSTALLED.





C31.1 WITH PRE-INSTALLED HANGER (2/S5.4) SLIDES INTO B18 @ C/7.5





C31 SLIDES WEST INTO KNIFE PLATE (6/S5.2) @ B/7.5
































































NOTE: ELEVATOR COLUMNS
AND THIS SHORT BEAM
INSTALLED PRIOR TO 1ST
ROOF PANEL BEING SET






















WALL	WALL ID	ALUMINUM	HEIGHT	HEIGHT
08-00	AP140	47	175-192	2395
08-00	AP140	48	175-192	2415
08-00	AP140	49	175-192	2435
08-04	244	1	B to Column	184
08-04	244	2	B to Column	184
08-04	245	3	B to Column	195
08-04	245	4	B to Column	195
08-04	246	5	B to Column	195
08-06	138	6	D to 2nd Flr	861
08-06	138	7	D to 2nd Flr	861
08-06	139	8	D to 2nd Flr	861
08-06	139	9	D to 2nd Flr	861
08-06	138	10	D to 2nd Flr	861
08-06	137	11	D to 2nd Flr	861
08-06	137	12	D to 2nd Flr	861
08-06	137	13	D to 2nd Flr	861
08-06	137	14	D to 2nd Flr	861
08-06	137	15	D to 2nd Flr	861
08-06	137	16	D to 2nd Flr	861
08-06	137	17	D to 2nd Flr	861
08-06	137	18	D to 2nd Flr	861
08-06	137	19	D to 2nd Flr	861
08-06	137	20	D to 2nd Flr	861
08-06	137	21	D to 2nd Flr	861
08-06	137	22	D to 2nd Flr	861
08-06	137	23	D to 2nd Flr	861
08-06	137	24	D to 2nd Flr	861
08-06	137	25	D to 2nd Flr	861
08-06	137	26	D to 2nd Flr	861
08-06	137	27	D to 2nd Flr	861
08-06	137	28	D to 2nd Flr	861
08-06	137	29	D to 2nd Flr	861
08-06	137	30	D to 2nd Flr	861
08-06	137	31	D to 2nd Flr	861
08-06	137	32	D to 2nd Flr	861
08-06	137	33	D to 2nd Flr	861
08-06	137	34	D to 2nd Flr	861
08-06	137	35	D to 2nd Flr	861
08-06	137	36	D to 2nd Flr	861
08-06	137	37	D to 2nd Flr	861
08-06	137	38	D to 2nd Flr	861
08-06	137	39	D to 2nd Flr	861
08-06	137	40	D to 2nd Flr	861
08-06	137	41	D to 2nd Flr	861
08-06	137	42	D to 2nd Flr	861
08-06	137	43	D to 2nd Flr	861
08-06	137	44	D to 2nd Flr	861
08-06	137	45	D to 2nd Flr	861
08-06	137	46	D to 2nd Flr	861
08-06	137	47	D to 2nd Flr	861
08-06	137	48	D to 2nd Flr	861
08-06	137	49	D to 2nd Flr	861
08-06	137	50	D to 2nd Flr	861
08-06	137	51	D to 2nd Flr	861
08-06	137	52	D to 2nd Flr	861
08-06	137	53	D to 2nd Flr	861
08-06	137	54	D to 2nd Flr	861
08-06	137	55	D to 2nd Flr	861
08-06	137	56	D to 2nd Flr	861
08-06	137	57	D to 2nd Flr	861
08-06	137	58	D to 2nd Flr	861
08-06	137	59	D to 2nd Flr	861
08-06	137	60	D to 2nd Flr	861
08-06	137	61	D to 2nd Flr	861
08-06	137	62	D to 2nd Flr	861
08-06	137	63	D to 2nd Flr	861
08-06	137	64	D to 2nd Flr	861
08-06	137	65	D to 2nd Flr	861
08-06	137	66	D to 2nd Flr	861
08-06	137	67	D to 2nd Flr	861
08-06	137	68	D to 2nd Flr	861
08-06	137	69	D to 2nd Flr	861
08-06	137	70	D to 2nd Flr	861
08-06	137	71	D to 2nd Flr	861
08-06	137	72	D to 2nd Flr	861
08-06	137	73	D to 2nd Flr	861
08-06	137	74	D to 2nd Flr	861
08-06	137	75	D to 2nd Flr	861
08-06	137	76	D to 2nd Flr	861
08-06	137	77	D to 2nd Flr	861
08-06	137	78	D to 2nd Flr	861
08-06	137	79	D to 2nd Flr	861
08-06	137	80	D to 2nd Flr	861
08-06	137	81	D to 2nd Flr	861
08-06	137	82	D to 2nd Flr	861
08-06	137	83	D to 2nd Flr	861
08-06	137	84	D to 2nd Flr	861
08-06	137	85	D to 2nd Flr	861
08-06	137	86	D to 2nd Flr	861
08-06	137	87	D to 2nd Flr	861
08-06	137	88	D to 2nd Flr	861
08-06	137	89	D to 2nd Flr	861
08-06	137	90	D to 2nd Flr	861
08-06	137	91	D to 2nd Flr	861
08-06	137	92	D to 2nd Flr	861
08-06	137	93	D to 2nd Flr	861
08-06	137	94	D to 2nd Flr	861
08-06	137	95	D to 2nd Flr	861
08-06	137	96	D to 2nd Flr	861
08-06	137	97	D to 2nd Flr	861
08-06	137	98	D to 2nd Flr	861
08-06	137	99	D to 2nd Flr	861
08-06	137	100	D to 2nd Flr	861

MARCH 26 - APRIL 02


Activity	Start	End	Duration
DLT1256 Setup KIT Crane	26-Mar-19	28-Mar-19	3 Days
DLT1257 Erect 1st Floor Columns and Beams	26-Mar-19	28-Mar-19	3 Days
DLT1280 Erect 1st Floor Columns and Beams	26-Mar-19	28-Mar-19	3 Days
DLT1248 Erect 2nd Floor Columns and Beams Area A	01-Apr-19	01-Apr-19	1 Day
DLT1206 Set W/P	02-Apr-19	02-Apr-19	1 Day



APRIL 03 - APRIL 10

CLT ID	Task / Delivery and Stage	QTY	Start Date	End Date
CLT1300	Install 2nd Floor Columns and Beams Area B	1	04-Apr-19	04-Apr-19
CLT1310	Set WP 002 008 010 012 014 016 018 020	1	05-Apr-19	05-Apr-19
CLT1320	Install 2nd Floor Beams Area C	1	08-Apr-19	08-Apr-19
CLT1330	Deliver 80T Crane	1	09-Apr-19	09-Apr-19
CLT1340	Setup 255T Crane	1	10-Apr-19	10-Apr-19


QTY	ITEM No.	ASSEMBLY No.	MATERIAL	WTGHT (KG)
30	WP13	24	105 90-1	1373
30	WP14	25	105 90-1	404
30	WP15	26	105 90-1	347
30	WP16	27	105 90-1	1192
30	WP17	28	105 90-1	1172
30	WP18	29	105 90-1	649
30	WP19	30	105 90-1	1267
30	WP20	31	105 90-1	2579
30	WP21	32	105 90-1	1437
30	WP22	33	105 90-1	836
30	WP23	34	105 90-1	554
30	WP24	35	105 90-1	908
30	WP25	36	105 90-1	1309
30	WP26	37	105 90-1	862
30	WP27	38	105 90-1	2507
30	WP28	39	0 Fr 200x40	1044
30	WP29	40	0 Fr 200x40	1561
30	WP30	41	0 Fr 200x40	1581
30	WP31	42	0 Fr 200x40	1564
30	WP32	43	0 Fr 200x40	1438
30	WP33	44	0 Fr 200x40	1561
30	WP34	45	0 Fr 200x40	1561
30	WP35	46	0 Fr 200x40	1556
30	WP36	47	105 V	107
30	WP37	48	105 V	304
30	WP38	49	0 Fr 200x40	114
30	WP39	50	0 Fr 200x40	318
30	WP40	51	0 Fr 200x40	318
30	WP41	52	0 Fr 200x40	318
30	WP42	53	0 Fr 200x40	318
30	WP43	54	0 Fr 200x40	318
30	WP44	55	0 Fr 200x40	1077
30	WP45	56	0 Fr 200x40	708
30	WP46	57	0 Fr 200x40	1557
30	WP47	58	0 Fr 200x40	379
30	WP48	59	0 Fr 200x40	213
30	WP49	60	0 Fr 200x40	325
30	WP50	61	0 Fr 200x40	325
30	WP51	62	0 Fr 200x40	64
30	WP52	63	0 Fr 200x40	64
30	WP53	64	0 Fr 200x40	718
30	WP54	65	0 Fr 200x40	252
30	WP55	66	0 Fr 200x40	414



APRIL 11 - APRIL 15

CLT1280	Table 2, Cherry and Maple	1	1	10-Apr-19	10-Apr-19
CLT1360	Instal RP 000 000 000 000	1 <td>1 <td>11-Apr-19 <td>11-Apr-19 </td></td></td>	1 <td>11-Apr-19 <td>11-Apr-19 </td></td>	11-Apr-19 <td>11-Apr-19 </td>	11-Apr-19
CLT1370	Instal WP 000 000 000 000 000 000	1 <td>1 <td>12-Apr-19 <td>12-Apr-19 </td></td></td>	1 <td>12-Apr-19 <td>12-Apr-19 </td></td>	12-Apr-19 <td>12-Apr-19 </td>	12-Apr-19
CLT1280	Instal MP 000 000 000 000 000 000	1 <td>1 <td>15-Apr-19 <td>15-Apr-19 </td></td></td>	1 <td>15-Apr-19 <td>15-Apr-19 </td></td>	15-Apr-19 <td>15-Apr-19 </td>	15-Apr-19


CLT Level 03	BUNDLE	MANUFACTURE	ASSEMBLY No.	MATERIAL	WEIGHT [kg]
	00-00	0P130	90	175 VD-3	8044
	00-02	0P127	92	175 VD-3	4239
	00-03	0P131	101	175 VD-3	8059
	00-06	0P116	096	175 VD-3	8206
	00-05	0P130	104	175 VD-3	8159
	00-06	0P117	103	175 VD-3	8177
	00-07	0P147	94	105 VD-1	2564
	00-07	0P142	95	105 VD-1	3050
					43924



APRIL 16 - APRIL 17

CLT 1400	Final Delivery and Stage	1	1	16-Apr-16	16-Apr-16		
CLT 1400	Final PR	100	100	100	100	17-Apr-17	17-Apr-17

CLT Load ID	QUANTITY	PERMID PR No.	ASSEMBLY No.	MATERIAL	WEIGHT (kg)
	80	00108	86	105 VD-1	1729
	87	00182	87	105 VD-1	2045
	20	00105	20	105 VD-1	881
	90	00143	90	105 VD-1	1704
	100	00149	100	105 VD-1	1771
	101	00125	101	105 VD-1	1788
	102	00123	102	175 VD-1	1587
	105	00120	105	175 VD-1	2488
	108	00138	108	175 VD-1	2507
	114	00130	114	175 VD-1	2507
	100	00122	100	175 VD-1	2200
	110	00105	110	175 VD-1	2204
	112	00134	112	175 VD-1	2325
	115	00133	115	175 VD-1	2470



APRIL 18 - APRIL 22

ITEM	DESCRIPTION	QTY	UNIT	START DATE	END DATE
CLT-420	Instal RP	1	1	10-Apr-19	10-Apr-19
CLT-430	Derek 20CT Cuzco	1	1	22-Apr-19	22-Apr-19

ITEM NO.	NUMPR NO.	ASSEMBLY NO.	QUANTITY	WEIGHT (KG)
80-01	RP125	125	175 VP 1	6134
80-02	RP121	127	175 VP 1	2607
80-03	RP128	134	175 VP 1	6159
80-04	RP139	123	175 VP 1	2874
80-05	RP133	138	175 VP 1	6799
80-06	RP122	126	175 VP 1	2134
80-07	RP121	122	175 VP 1	6159
80-08	RP137	121	175 VP 1	6031
80-09	RP128	122	175 VP 1	6021
				44228

New DPR Sacramento Office

Mass Timber Logistics




PHOTOS

Final Product











Let's discuss form, function, and sustainability

This concludes The American Institute of Architects Continuing Education Systems Course.



Stephen Guest AIA, LEED AP
RMW architecture & interiors
sguest@rmw.com



Marshall Andrews, LEED AP
DPR Construction
marshalla@dpr.com

