# CLT in the U.S.

Manufacturing and Applications

Presented by: Levi Huffman P.E.



Disclaimer: This presentation was developed by a third party and is not funded by WoodWorks or the Softwood Lumber Board.

"The Wood Products Council" is a Registered Provider with The American Institute of Architects Continuing Education Systems (AIA/CES), Provider #G516.

Credit(s) earned on completion of this course will be reported to AIA CES for AIA members. Certificates of Completion for both AIA members and non-AIA members are available upon request. This course is registered with AIA CES for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.

Questions related to specific materials, methods, and services will be addressed at the conclusion of this presentation.



#### **Course Description**

Architects around the world are using mass timber construction systems to build taller wood buildings, incorporate the aesthetic of exposed wood, or increase the amount of prefabrication on their projects. Many use crosslaminated timber (CLT) panels and glue-laminated timber (glulam) beams as the building structure, often as a carbon-friendly alternative to conventional materials such as steel, masonry and concrete. In this presentation by DR Johnson, successful U.S. projects will be highlighted to demonstrate the variety of commercial and multi-family applications available for CLT under today's building codes. Topics will also include CLT manufacturing, benefits such as structural versatility, and potential future uses.





#### What is Cross Laminated Timber?



- Secondary Wood Product
- Several layers of lumber stacked crosswise
- Bonded together with structural adhesive
- ▶ Generally 3, 5, 7, or 9 layers thick

Ref: Fig 1, CLT Handbook: Cross Laminated Timber. FPInnovations (2013).







### CLT - Manufacturing













#### **CLT** Product Standard

Consensus standard

Sets minimum performance requirements

Requires independent 3<sup>rd</sup> party inspection

Gives code officials assurance

Designers focus on design & innovation

ANSI/APA PEG 320-2018

#### Standard for Performance-Rated Cross-Laminated Timber

NATIONAL STANDA



#### ANSI/APA PRG 320 – Key Considerations

Dry-use

12% Moisture Content

```
Lamination thickness: 5/8" to 2"
```

```
Size Tolerances: Thickness = 1/16", Width = 1/8", Length = 1/4"
```

Adhesives: sets fire performance criteria

Standard grades of CLT









### CLT Manufacturing







11/12/2019



## CLT – Lifting Anchors













#### CLT in Building Codes - 2015 & 2018 IBC

#### CLT permitted in various Types of Construction

CLT Floors			√	$\checkmark$	./
					v
CLT Roofs (1-	✓ -hr or less FRR)	✓ (1-hr or less FRR)	$\checkmark$	$\checkmark$	$\checkmark$
CLT interior walls			V	$\checkmark$	$\checkmark$
CLT exterior walls				$\checkmark$	$\checkmark$

#### 2021 IBC - Proposed Changes

#### Modernizing Type IV Heavy Timber for Tall Wood Buildings

Type of Construction	Max Height	# Stories	Exposed Mass Timber	Primary Frame FRR	Floor FRR	Stair Tower	Concealed Spaces
IV-HT	85 ft	4-6	fully exposed	HT (2021)	HT	Mass Timber	Permitted (2021)
IV-C	85 ft	4-9	fully exposed	2 hr	2 hr	Mass Timber	Permitted
IV-B	180 ft	6-12	partially exposed	2 hr	2 hr	Mass Timber	Permitted
IV-A	270 ft	9-18	fully protected	3 hr	2 hr	Noncombustible	Permitted
	Courtesy of: Am erican W ood Counc						

### **CLT** - Benefits

- Renewable Resource
- Alternative to Concrete/Steel
- Flexible Design
- Fast Installation
- Fire & Seismic Performance



#### **Domestically Grown**

- Support US Forest economy
- Revitalize rural communities



#### Sustainability

- Wood buildings store carbon (50% of dry wood weight is carbon)
- Wood buildings currently store 5.4 billion tons of carbon
- Lighter, higher precision, and faster construction time compared to concrete
- Sustainable forest management

#### **CLT** Installation

- Small Crews
- Rig, pick, set, secure










11/12/2019







11/12/2019







11/12/2019











## **Delivering Success**

- Logistics and Trucking Plans
- Regular communication of Schedule
- Trained Installation Crew





#### Sonoma Academy

Janet Durgin Guild & Commons

Owner: Sonoma Academy Architect: WRNS Studio Structural Engineer: Mar Structural General Contractor: XL Construction Timber Supplier: DR Johnson Location: Santa Rosa, California





Credit: W RN S Studio



## Sonoma Academy - Roof

- CLT & steel hybrid
- Exposed CLT soffit



## Sonoma Academy - CLT install

- Laydown area
- Small crew



## Sonoma Academy - CLT curve

- Coordination between design team, steel and timber fabricators
- Tolerances



# Sonoma Academy – CLT to steel detail







# Sonoma Academy



# Albina Yard

Owner/ GC: Reworks Architect: LEVER Architecture Structural Engineer: KPFF Timber Supplier: DR Johnson Timber Fabrication: DR Johnson(CLT) CutMyTimber (Glulam)

Project Support: WoodWorks









- CLT panels up to 10' x 24'
- CLT cantilevers 4'
- Glue-laminated frame





# Albina Yard - Hundegger CNC -

#### Albina Yard - Digital Fabrication

- CNC routed
- Tight tolerances







## Albina Yard - 16,000 sf Office


## Albina Yard - CLT Central Stair



## Albina Yard – Illuminating the path for more CLT in the U.S.

Early involvement of GC & fabricators Efficient panel layout Coordinating all MEP penetrations before fabrication Accurate BIM model Tolerances between trades GC to pre-plan everything Extremely fast construction

















## Mass Timber – Future Applications

- Mid-rise commercial and multi-unit housing
- Modular construction
- Military buildings
- Buildings beyond 20 stories





