

RISD Quad New Residence Hall

Key Project Challenges

- Schedule and speed
- Aggressive institution wide sustainability goals
- Adjacent concrete flat plate dormitories
- Design goal to create artist loft experience
- Interest in mass timber



Glued Laminated Timber



Structural Composite Lumber



Panelized Wood Products



Cross Laminated Timber



Dowel Laminated Timber











Cross Laminated Timber

- Made with sapling lumber
- Manufactured in up to 65' lengths
- Two-way action possible
- Sequestered carbon





All heights assume NFPA 13 sprinkler system

IBC2015 Construction Types

FPA 13 prinkler /stem	Type 1 Noncombustible		Type 3 Noncombustible/ Combustible		Type 4 Heavy Timber	Type 5 Combustible	
Occupancy	Α	В	Α	В		Α	В
A,B,R	None	180'	85'	75'	85'	70'	60'
A-2, A-3 A-4	None	12	4	4	4	3	2
В	None	12	6	4	6	4	3
R-2	None	12	5	5	5	4	3

Can use
Mass
Timber in
ALL types


Height Limit



A: Interior structure fire rated

B: Interior mostly unrated

Height Limits – Type 3 and Type 4



Residential Dormitory (R-2)

Minimum Heavy Timber Sizes (Type 4)

Member Type	Floor Framing	Roof Framing
Column	8x8	6x6
Beam	6x10	6" minimum thickness
Floor Deck (solid or glu- lam)	4" nominal	2" nominal
Cross laminated timber	4" actual	3" nominal

MINIMUM NOMINAL SOLID SAWN SIZE		MINIMUM GLUE NET	ED-LAMINATED SIZE	MINIMUM STRUCTURAL COMPOSITE LUMBER NET SIZE	
Width, inch	Depth, inch	Width, inch	Depth, inch	Width, inch	Depth, inch
8	8	63/4	81/4	7	71/2
6	10	5	101/2	51/4	91/2
6	8	5	81/4	51/4	71/2
6	6	5	6	51/4	51/2
4	6	3	67/,	31/,	51/,


Choosing by Advantages

Options

- Girder-slab (precast concrete with steel)
- All glued laminated timber frame and decking
- Steel-CLT hybrid

Key Factors


- Speed of construction
- Sustainability
- Aesthetic "look and feel"
- Cost
- Span and depth of members



Overview: Hybrid CLT-Steel Construction


Features

- Steel frame with CLT slabs
- One-way CLT panels entire building width
- Construction Type
 - Type 1A construction Below Lvl 2
 - Type 3B construction Above Lvl 2
- Exposed CLT ceilings
- Topping slab and acoustic isolation mat for sound isolation




Floor Assembly – Acoustic Separation

- IBC 2015 Sound Transmission (1207)
 - Sound Transmission Class >= 50
 - Impact Insulation Class >=50
- Final Assembly (USG Products):
 - USG Levelrock SAM-N25 Ultra –
 Sound Attenuation Mat
 - USG Levelrock Sound Reduction Board
 - USG Levelrock 3500 Floor
 Underlayment (2" min thickness)



CLT in Exterior Wall Assembly

- IBC 2015 Requirements (602.4)
 - Allowed in walls with 2 hour rating or less
 - Must be protected on exterior surface













Constructability Considerations


Key Issues


- Mix of trades wood and steel erector
- Fasteners chosen for speed
- Most holes field drilled simplifies coordination
- Diaphragm design using spline connectors





All field connections bolted







Unframed openings in floors



Coordination of MEP systems









Exterior Skin Construction



Exterior Skin Construction

THE CATEGORISH SHEET SHE

AM COLD MARKETY; -











Photo by John Horner





Photos by John Horner



Photo by John Horner



Photos by John Horner

Questions?

Rendering courtesy of NADAAA, Inc.

