# The Duke: Mass Timber & Light Frame Hybrid

Presented by Forrest Bratton, P.E., SECB



Disclaimer: This presentation was developed by a third party and is not funded by WoodWorks or the Softwood Lumber Board.

#### The Duke: Project Team

Owner:

Harris Bay; Granite Bay, CA
Architect:
DesignTrait; Austin, TX
Structural Engineer:

WGI; Austin, TX

MEP Engineer:

AYS; Austin, TX

General Contractor:

Trinity Constructors; Pflugerville, TX Mass Timber Supplier: KLH US Holding Corp.; Portland, OR



## The Duke: The Brief

Design and construct an *all-timber* 4-story mixed-use building in the heart of the fast-developing East Side of Austin, Texas

Considerations:

- Ground floor retail needs "open" floor plan, minimal walls
- Residential units to have maximal ceiling heights
- Timber structure to be exposed wherever possible
- High local familiarity with light-framed wood construction
- Mass timber desired as proof-of-concept, interest-generation

# The Duke: Building Stats

Building Code:

• 2015 IBC

Building Height:

• 4 stories, 57'-0" tall

Building Area:

- 41,989 SF conditioned
- 1,179 SF patios

Construction Type

- IV at 1<sup>st</sup> floor, VA above
- (could have been VA throughout)

Occupancy:

- Ground Floor: A-2, B, M (Food service, Business, Mercantile)
- Upper Floors: R-2 (Long-term Residential)



# The Duke: The Concept

*Options considered during concept:* 

- Concrete Podium +
   Light-framed wood (traditional)
   Light-framed wood + mass timber (hybrid)
- All heavy timber •

Timber "Podium" + Light-framed wood (traditional)
 Light-framed wood + mass timber (hybrid) +

# The Duke: The Concept

#### Timber "Podium" + Light-framed wood + mass timber (hybrid)

Challenges

- Unfamiliar construction methods for local contractors
  - Accepted as part of process to develop proof-of-concept  $\rightarrow$  more on this later
- Timber "podium" cannot provide 3-hour fire separation at Level 2
  - 1-hour rating sufficient for separation between occupancies, provided through char per NDS
  - NFPA 13 sprinklers must be provided at all levels
- Deeper structure required for Level 2 than comparable concrete
  - Maximum building height not a controlling criterion for project
  - Lower clear height between (typ. 33") girders deemed acceptable
- Closer column spacing required than for concrete podium slab
  - Accepted because exposed timber viewed as a feature


# The Duke: The Concept


#### Timber "Podium" + Light-framed wood + mass timber (hybrid)


Advantages

- In keeping with all-timber brief, opportunity for added value
- Lighter than concrete podium options (foundation savings—clay subgrade)
- Faster to erect than cast-in-place concrete
- Optimizes use of wood fiber vs all-mass-timber option
- Flexible layout of residential units
- Walls can incorporate plumbing/electrical as with traditional wood-frame construction
- Fewer separate elements/connectors for lateral structural system


### The Duke: Gravity Structure









## The Duke: Gravity Structure






Level 2 CLT panels (280mm "podium" floor) Glulam Girders & Columns CLT walls (140mm, 200mm)

#### The Duke: Lateral Structure




Upper CLT panel diaphragms (160mm floors, 120mm roof)



Light-framed wood shear walls (Mix of wood panel and gypsum sheathing)

#### The Duke: Lateral Structure



#### Level 2 CLT panels (280mm "podium" floor)

CLT walls (140mm, 200mm)


### The Duke: Sample Details


1. CLT FLOOR PLATE 2. 1" 3-LAYER SPRUCE SPLINE

CONSTRUCTION ADHESIVE

#### Simple spline joints are used at upper-level panels.

#### Screws installed from above connect through panels to walls below.





1. CLT FLOOR PLATE 2. FIN. FLOOR REF. ARCH 3. STUD WALL 4. WALL PLATES 5. EXTERIOR SHEATHING 6. 14'10 ASSY ECOFAST SCREWS @10' O.C. SCREW LENGTH: 8.58' @160mm PANEL 7. 18' @120mm PANEL


#### TYPICAL DETAIL CLT SPLINE CONNECTION LEVELS 3,4, AND ROOF SCALE: 1"= 1"-0"

#### EXTERIOR FLOOR FRAME DETAILS


SCALE: 1\* = 1'-0\*

## The Duke: Sample Details


#### Inclined screws are used for wall connections occurring at panel joints.



## Half-lap joints with inclined screws at Level 2 provide better load-sharing and diaphragm stiffness.



1. CLT PANEL 4 2. 45" INCLINED SWG ASSY VG Cyl 3/8"0% 15" SCREWS @12" O.C. 3. VERTICAL SWG ASSY VG CSK 5/16"0% 10 1/4" SCREWS @12" O.C. FOR PANEL EDGE REINFORCEMENT 4. CONSTRUCTION ADHESINE



LEVEL 2 PANEL HALF-LAP JOINT TYPICAL DETAIL

SCALE: 1\* = 1'-0\*

## The Duke: Sample Details

#### Shear wall holdowns use screw plates welded to threaded rod base connectors.

#### Inclined screws fasten collector straps and attach Level 2 panels to CLT shear walls

1. CLT FLOOR PANEL

SEGMENTS, TYP.

WHERE NO STRAP OCCURS OVER

OPEN

WALL, PROVIDE SAME SCREW

WITHOUT WASHERS

CONNECTION, BUT TYPE VG Cyl

3 PL 5/16'x5' CONT. COLLECTOR STRAP

45° WASHERS AT STRAPPING NOT

REQ'D, PROVIDE STRAP IN 20-FT

A

(1)

OVER A WALL. WHERE SPLICES ARE

CSK SCREWS @12" O.C. w/ 45" WASHERS OVER WALL PER PLAN, USE CROSSING PAIRS OF 3/8"Ø x 12 5/8" ASSY VG CSK SCREWS @18" O.C. w/

w/ (2) ROWS OF 3/8"Ø x 25 5/8" ASSY VG

2. CLT WALL


(18) 3/8"Ø x 3 1/8"

ASSY ECOFAST

SCREWS

ш

1 1/2" TYP.





PLAN VIEW

(4)

(3)(5)

(2)

#### TYPICAL DETAIL ROD HOLDOWN CONNECTION AT CLT PLATE SCALE: 1 1/2" = 1'-0"

#### COLLECTOR STRAP AND CLT FLOOR PANEL CONNECTION TO CLT SHEAR WALL TYPICAL DETAIL


(2)

SCALE: 1" = 1'-0"

## The Duke: Special Considerations

- Fire separation between residential units with exposed CLT/timber
- Waterproofing CLT at exterior balconies
- Performance of CLT as diaphragm/shear wall
- Floor vibrations, especially across units
- Concentrated loads on CLT panels
- Acoustic performance of CLT floor


#### Mass timber floors need sound attenuation, particularly between residential units.



- Buildup over CLT to achieve minimum STC 55 and IIC 55 ratings with exposed timber panel ceilings.
- Poured underlayment avoided due to weight and potential schedule impact due to cure time.\*
- Assembly was value-engineered during bidding, but viable alternative proved difficult to find.

\*After start of construction, design team learned that GC would have preferred a poured topping for greater simplicity (but weight is still an issue).

#### WoodWorks has a resource for acoustically-tested assemblies.



#### **Acoustically-Tested Mass Timber Assemblies**

Following is a list of mass timber assemblies that have been acoustically tested as of May 11, 2021. Sources are noted at the end of this document. For free technical assistance on any questions related to the acoustical design of mass timber assemblies, or free technical assistance related to any aspect of the design, engineering or construction of a commercial or multi-family wood building in the U.S., email help@woodworks.org or contact the WoodWorks Regional Director nearest you: http://www.woodworks.org/project-assistance

#### Contents:

Table 1: CLT Floor Assemblies with Concrete/Gypsum Topping, Ceiling Side Exposed	
Table 2: CLT-Concrete Composite Floor Assemblies, Ceiling Side Exposed	9
Table 3: CLT Floor Assemblies without Concrete/Gypsum Topping, Ceiling Side Exposed	
Table 4: CLT Floor Assemblies without Concrete/Gypsum Topping, with Wood Sleepers, Ceiling Side Exposed	
Table 5: NLT, GLT, MPP & T&G Decking Floor Assemblies, Ceiling Side Exposed	
Table 6: Mass Timber Floor Assemblies with Ceiling Side Concealed	
Table 7: Single CLT Wall	25
Table 8: Single NLT Wall	
Table 9: Double CLT Wall	
Sources	
Disclaimer	

#### Poured toppings were too heavy to use for as a late alternative. (12 psf max)

	CLT Panel	Concrete/Gypsum Topping	Acoustical Mat Product Between CLT and Topping	Finish Floor	STC <sup>3</sup>	IIC <sup>1</sup>	Source				
			Pliteq GenieMat <sup>™</sup> FF16 (FF10 + FF06)		56	50	32				
			Pliteq GenieMat™ FF20 (FF10 + FF10)		57	51	51 30				
		4" concrete	4" concrete	4" concrete		Pliteq GenieMat <sup>w</sup> FF23 (FF17 + FF06)	None	56	52	33	
							57	50	2		
	CLT 5-ply (6.875")				4" concrete	Pliteq GenieMat <sup>**</sup> FF25	Eng Wood on GenieMat <sup>ne</sup> RST02	56	55	29	
			Pliteg GenieMat™ FF31 (FF25 + FF06)	None	58	53	34				
					59	54	54 2				
			Pliteq GenieMat'* FF50 (FF25 + FF25)	Eng Wood on GenieMat™ RST02	58	59	5				
19 psf ———				LVT	-	546	122				
			Keene %" Quiet Qurl* 075	LVT on 1" Platform L2	2	60°	121	— No STC rating			
		2" gypsum	Keene 3/8" Quiet Qurl® 040	Underlayment on 5mm KeedeRoll MT Premium		586	124				
			5 mm Keene Step Soft Underlayment on Keene %" Quiet Qurl® 075	LVT	-	56 <sup>6</sup>	123				
		\$1 ····································	An			10 10 10					
			Kinetics" RIM-33L-2-24 System with %" Plywood	None	61	46	112				
				LVT	-	61	113				
38 psf ———				2 layers of %" USG Fiberock® on Kinetics® Soundmatt	61	59	114				
	CLT 5-ply (6.0")			LVT on 2 layers of %" USG Fiberock® on Kinetics® Soundmatt	•)	59	115				
		3" concrete	concrete	None	59	46	116				
				LVT	-	58	117				
		inetics <sup>®</sup> Ultra Quiet SR with synthetic roofing felt	2 layers of ¼" USG Fiberock® on Kinetics® Soundmatt	61	58	118					
				LVT on 2 layers of %" USG Fiberock® on Kinetics® Soundmatt		57	119				
		4" concrete	Kinetics® RIM-33L-2-24 System with %" Plywood	None	61	52	120				

#### Only pre-drill plumbing penetrations where you are 100% sure you have it right.

- If coordinated early, it is easy to pre-core plumbing penetrations, BUT...
- If penetrations are located incorrectly, enlarging holes can be difficult. Cutting/coring also removes more of the structural member, which must be reanalyzed.
- Location/size information is likely communicated to manufacturer via CAD, which is atypical for a formal design deliverable. Scope appropriately, and consider liability implications.
- Contractor may prefer to drill/core all penetrations in field (may need special equipment; EOR must review layout)



#### Communicate early to verify elevator can be installed as intended.


- Elevator installer may want entire shaft width open at first level for cab installation, BUT...
- If CLT wall is loadbearing and a shear wall then what? (door opening comparable to concrete shaft)
- Also consider guide rail bracket attachment may be nonstandard















# > HOLD YOUR QUESTIONS!

This concludes The American Institute of Architects Continuing Education Systems Course

Forrest Bratton, P.E., SECB

WGI, Inc.

Forrest.Bratton@wginc.com