

# Penn State College of Engineering West 2 The Innovation & Making Hub

November 4, 2021

Presented By:


Jennifer Hardy  
Adam Green

PAYETTE

**WT**  
WHITING-TURNER

Disclaimer: This presentation was developed by a third party and is not funded by WoodWorks or the Softwood Lumber Board.





**WEST CAMPUS**

**CoE WEST**

**CoE CORE**

**CORE CAMPUS**

**SHORTLIDGE**

**POLLOCK ROAD WALK**

**OLD MAIN**


**DOWNTOWN  
STATE COLLEGE**

**ATHERTON ROAD**

**State College**







SERVICE  
AREA

WEST 1

EES

WESTGATE

WEST DECK  
GARAGE

HIGH  
BAY

WEST 2

WEST QUAD

A&B

RESEARCH WEST

LEONHARD






# The Innovation & Making Hub for the College of Engineering

## Mass Timber Enhancing Project Goals

- Building as a **teaching tool**
- **Forward-looking** design
- Real-life **engineering** problems
- A **toolbox** for all scales of making
- Pedagogy of **innovative thinking**
- Innovation in **construction technology**
- **High visibility** with **energy efficiency**



Engineer's Toolbox



# A Toolbox for all Scales of Making




Large open column-free build spaces

Flexibility & adaptability of use

Aspirational design elements as a teaching tool

Environment for cornerstone to capstone engineering

Design from concept to industry partnership










Innovation on Display






# Timber Curtain Wall






# Thermal Performance & Comfort


ALUMINUM + TRIPLE GLAZING  
 $U = 0.25$



TIMBER + TRIPLE GLAZING  
 $U = 0.14$




TIMBER + DOUBLE GLAZING  
 $U = 0.22$





# Performance Based Embodied Carbon Savings









# Wood Palette

## History of Making

- Heavy timber industrial mill buildings with large open interior floor plans
- Industrial use of wood flooring for durability

## Targeted Embodied Carbon Reduction

## Health & Wellness of Occupants

## Biophilic Benefits

## Beauty







# Hybrid Structure

High Bay:  
REINFORCED CMU &  
STEEL FRAMING

Roof:  
STEEL DECK &  
STEEL FRAMING

Levels 1,2,3,4:  
CLT DECK  
ON STEEL FRAMING

Basement:  
CONCRETE  
FOUNDATION &  
SLAB ON GRADE

























# Competitive Bidding Considerations

CLT species, stress grade, panel size & thickness, ANSI/APA PRG 320 certification

Glulam options compatible with timber curtain wall

Responsibly sourced wood availability from different manufacturers

Factory vs. field applied sealant for moisture mitigation depending on manufacturer

Acoustic floor assembly options with equal performance and dimensions





# Floor Assembly

Availability of wet vs. dry acoustic assemblies



Concrete vs. gypcrete

Finish floor subfloor requirements

Acoustic performance and dimensional variability in products

Performance-based concrete topping (low embodied carbon)

Adequate depth for floor boxes and conduit









# Intersection of CLT & Steel





# Bidding the Packages

Cross Laminated Timber:

- 1) Packaging CLT with Structural Steel
- 2) Pre-Qualification Process
- 3) Pre-Bid and Scope Review Meetings
- 4) Education of All Trades


Timber Curtainwall:

- 1) Packaging with all glazing
- 2) Locked into local, small firm

## V. PROJECT OVERVIEW / DRAWINGS AND SPECIFICATIONS

### ■ Cross-Laminated Timber Decking

- No permanent markings on the bottom
- Approved hangers only
- Remove water
- All penetrations need to be approved by the CLT Engineer
- Will receive a concrete topping slab
- **THIS IS A FINISHED PRODUCT AND WILL BE EXPOSED FROM BELOW**







# Pre-Construction Phase

Cross Laminated Timber:

- 1) Immediate vendor buy-in
- 2) Pre-Construction / Pre-Installation Meetings
  - 1) During MEP coordination
  - 2) Prior to manufacturing
  - 3) Factory visit (attempted)
  - 4) Prior to shipping





# Pre-Construction Phase

Timber Curtainwall:

- 1) Immediate vendor buy-in
- 2) Pre-Construction / Pre-Installation Meetings
  - 1) Prior to steel installation
  - 2) Before material release
  - 3) Factory visit





# Installation of CLT

- 1) Moisture Management Plan
  - a) Develop
  - b) Maintain
  - c) Lessons Learned
    - i) Review every condition
    - ii) Adjust to site conditions
- 2) Ease of Installation
  - a) Quick learning curve
- 3) Open Communication
  - a) “Lean” problem solving
- 4) Preservation of CLT Underside









# QUESTIONS

This concludes The American Institute of Architects Continuing Education Systems Course

Presented By:

Jennifer Hardy, AIA, LEED AP BD+C

Payette

[jhardy@payette.com](mailto:jhardy@payette.com)

Adam Green

The Whiting-Turner Contracting Company

[Adam.Green@whiting-turner.com](mailto:Adam.Green@whiting-turner.com)

