Designing and Building with Mass Timber: Design, Planning and Performance

Presented by: **Anthony Harvey, PE Brandon Brooks, MBA, PMP** WoodWorks July 22, 2022



John W. Olver Design Building at UMass Amherst, Leers Weinzapfel Associates, Equilibrium Consulting, photo Alexander Schreyer

Questions? Ask me anything.



Anthony Harvey, PE Regional Director | OH, IN, KY, MI (513) 222-3038 anthony.harvey@woodworks.org



Brandon Brooks, MBA, PMP Construction Management Program Manager (760) 271-3722 brandon.brooks@woodworks.org

WOODWORKS

901 East Sixth, Thoughtbarn-Delineate Studio, Leap!Structures, photo Casey Dunn

"The Wood Products Council" is a Registered Provider with The American Institute of Architects Continuing Education Systems (AIA/CES), Provider #G516.

Credit(s) earned on completion of this course will be reported to AIA CES for AIA members. Certificates of Completion for both AIA members and non-AIA members are available upon request. This course is registered with AIA CES for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.

Questions related to specific materials, methods, and services will be addressed at the conclusion of this presentation.



Course Description

How can architects, engineers and contractors collaborate to meet the growing demand for mass timber buildings? While developers across the country are pursuing mass timber projects, knowledge among AEC professionals is not yet widespread. Firms have varying degrees of familiarity with both the products and practicalities of designing, sourcing, and building a modern mass timber structure, and early adopters continue to play a significant role in educating the rest of the community. This presentation seeks to build on this openness and environment of shared learning, providing an overview of mass timber products, planning, design and implementation to maximize the benefits these buildings can deliver. We'll also discuss why some mass timber projects face resistance, and how to overcome misconceptions to achieve success. Topics will also include preconstruction coordination and interactions between the manufacturer and design/construction teams, case-based approaches to costing and scheduling, project delivery methods, how to achieve the highest level of efficiency for costs, schedule, and performance, and additional education and training opportunities.

Learning Objectives

- 1. Identify project planning, coordination and design topics that translate into successful buildings for both the design and construction team.
- 2. Explore best practices for interaction between manufacturer, design team and preconstruction manager that can lead to cost efficiency and safety on site.
- 3. Discuss potential construction schedule savings and construction fire safety practices realized through the use of prefabricated mass timber elements.
- 4. Discuss benefits of using mass timber products, including structural versatility, prefabrication, lighter carbon footprint, and reduced labor costs.

PRESENTATION OUTLINE

MASS TIMBER DESIGN Products Structural Solution & Connections Projects and Code Considerations

MASS TIMBER CONSTRUCTION Planning for Construction Performing Construction Workforce Development

MASS TIMBER OVERVIEW


Photo: PCL Construction

COTT &

OVERVIEW | TIMBER METHODOLOGIES







Light Wood-Frame Photo: WoodWorks Heavy Timber Photo: Benjamin Benschneider

Mass Timber Photo: John Stamets

MASS TIMBER PRODUCTS

Glue Laminated Timber (Glulam) Beams & columns

Cross-Laminated Timber (CLT) Solid sawn laminations

Cross-Laminated Timber (CLT) SCL laminations








Photo: Freres Lumber







Dowel-Laminated Timber (DLT)



Nail-Laminated Timber (NLT)



Glue-Laminated Timber (GLT) Plank orientation




Photo: Think Wood

Photo: StructureCraft




Glue Laminated Timber (GLT)



Glue Laminated Timber (GLT)



Photo: Manasc Isaac Architects/Fast + Epp




Cross-Laminated Timber (CLT)



Cross-Laminated Timber (CLT)

With solid sawn laminations




Cross-Laminated Timber (CLT)

With SCL laminations





Nail-Laminated Timber (NLT)





Dowel-Laminated Timber (DLT)



Other Mass Timber Product Options



Glue Laminated Timber GLT Laminated Veneer Lumber LVL Parallel Strand Lumber PSL Laminated Strand Lumber LSL




Timber-Concrete Composite TCC



Photos: StructureCraft



STRUCTURAL SOLUTIONS | POST, BEAM + PLATE




STRUCTURAL SOLUTIONS | POST + PLATE



STRUCTURAL SOLUTIONS | HONEYCOMB




STRUCTURAL SOLUTIONS | HYBRID LIGHT-FRAME + MASS TIMBER



FRAMING OPTIONS | HYBRID STEEL + MASS TIMBER



STRUCTURAL SOLUTIONS | HYBRID STEEL + MASS TIMBER



STRUCTURAL SOLUTIONS | HYBRID CONCRETE + MASS TIMBER





the New York, and the same party that the same same

Self Tapping Screws

Photo Marcus Kauffman

Photo Simpson Strong Tie



Photo: Structurlam



Photo: Alex Schreyer






Panel to Panel & Supports

Photo: Charles Judd

Photo: Marcus Kauffman


Current State of Mass Timber Projects

As of March 2022, in the US, **1,384** multi-family, commercial, or institutional projects have been constructed with, or are in design with, mass timber.




Current State of Mass Timber Projects

As of March 2022, in the US, **1,384** multi-family, commercial, or institutional projects have been constructed with, or are in design with, mass timber.



Brock Commons



INTRO, CLEVELAND

9 Stories | 115 ft 8 Timber Over 1 Podium

Wash.

512,000 SF 297 Apartments, Mixed-Use

Photo: Harbor Bay Real Estate Advisors, Purple Film | Architect: Hartshorne Plunkard Architecture

INTRO, CLEVELAND

9 Stories | 115 ft 8 Timber Over 1 Podium

Type IV-B Variance to expose ~50% ceilings

Photo: Harbor Bay Real Estate Advisors, Image Fiction | Architect: Hartshorne Pl

ard Architecture 🥣

ASCENT, MILWAUKEE

Photo: Korb & Associates Architects | Architect: Korb & Associates Architects

493,000 SF 259 APARTMENTS, MIXED-USE

ASCENT, MILWAUKEE

Tallest Mass Timber Building in the World



Photo: CD Smith Construction | Architect: Korb & Associates Architects

80 M ST, WASHINGTON, DC

3 STORY VERTICAL ADDITION 7 STORY EXISTING BUILDING

Photo: WoodWork Architect: Hickok Cole

80 M ST, WASHINGTON, DC

100,000 SF 2 NEW LEVELS OF CLASS A OFFICE SPACE OCCUPIED PENTHOUSE 17'-0" CEILING HEIGHTS

APEX PLAZA CHARLOTTESVILLE, VA

187,000 SF

Photo: WoodWorks | Architect: William McDonough + Partners

APEX P CHARLOT **TESVILLE, VA**

8 STORIES 6 TIMBER OVER 2 PODIUM, 100 FT

Photo: William McDonough + Partners | Architect: William McDonough + Partners

PRIMARILY OFFICE SPACE

Gleason st

11 E LENOX, BOSTON, MA

TAXABLE AND ADDRESS OF ADDRESS OF

7 STORIES 70 FT Passive House Multi-Family

Credit: H + O Structural Engineering

11 E LENOX, BOSTON, MA

work of a contract

Credit: H + O Structural Engineering

CHURCHES CAUGES CAUGES

CHUNSER CHUNSER CHUNSER CHUNSER

Test





Photos: StructureCraft

Photo: Hartshorne Plunkard Architectur


PRECEDENT PROJECTS | T3 ATLANTA

MASS TIMBER PROJECT CONSIDERATIONS

Photo: Hacker Architects


MASS TIMBER IN THE CODE

Mass Timber in Low- to Mid-Rise: 1-6 Stories in Construction Types III, IV or V



BUILDING CODE APPLICATIONS | CONSTRUCTION TYPE

Tall Mass Timber: Up to 18 Stories in Construction Types IV-A, IV-B or IV-C




BUILDING CODE APPLICATIONS | FIRE RESISTANCE


Table 16.2.1AChar Depth and Effective CharDepth (for $\beta_n = 1.5$ in./hr.)

Mass Timber's Fire-Resistive Performance is Well-Tested, Documented and Recognized via Code Acceptance

Required Fire Resistance (hr.)	Char Depth, a _{char} (in.)	Effective Char Depth, a _{eff} (in.)
1-Hour	1.5	1.8
1 ¹ / ₂ -Hour	2.1	2.5
2-Hour	2.6	3.2

Source: AWC's NDS







BUILDING CODE APPLICATIONS | FIRE RESISTANCE



Demonstrating Fire-Resistance Ratings for Mass Timber Elements in Tall Wood Structures

Changes to the 2021 international Building Code (BIC) have invalided experimentals for seven buildings. Not an much larger and takes that proceeding allowed in part writing at the code. Occurrent party, and the interior to ansate the performance in performance and approved. The transition of the changes were developed and approved. The result is there are calculated for the processes the seven in the changes were developed and approved. The result is there are calculated for the processes the performance of the changes are based on the processes. Hence, the seven is the seven the processes the seven is the seven based on the processes. Hence, the seven is the seven the processes. Hence, the seven is the seven based on the processes.

Does of the main weigh to demonstrate that a bailding with need the required level of parametric transition registrations of directivant meteriosis, its through heavy frerelations ratings (FRRs) of its elements and assemblies. This IBC partners, an FRR as the pancial of time a bailing channel, component or assembly requirements for satisfy to confine a free, combiners to perform a generic diractment function, or both, so determined by the text), or the methods present on instru-

FBBs for this row construction types are similar to those required for type London/cone, which is primarily each and concersi-' (See Tobin 1) They are found to BC. Tatos 901, which includes, FBR requestioners for all complexities hypes and building elements. Insurement, other under



Antis & FRR Requirements (Hours) for Tail Mass Tailan Communition Types and Existing Type 1

Raining Deriver Language and Institute and I		NA Adam. 10 processi 274.4 274.500 pt ^{ala}	1.0 May 12 parameter (0.0 M and 10 and 10	No. 17 person Mar. 17 person Mar.A. 210-000 vite	Mic Alex. Pyteresi SP 8 COLUMN at 1	
Prenally Frame	3	3	2	2	3	
Enviro Brierry Mark		3	2	2.11	3	
interior Rearing Male		1.	2	2	1	
Rold Carlsharton	13	18	1	1	1	
Printing Franks in Board	3	3.	1	1	9.1	
Poor Construction	2	2.	17	18	20 CT	

Applyment at NFPA 13 automate spontenet system throughtaid building "Onlineased building day paymentated for mask payments.

Process TV Re R. S 11112 (2017) Incomed 1011 (1000) (11, 800000) (C. Removed et announ II 1000 and 8100000)

Mass Timber Fire Design Resource

- Code compliance options for demonstrating FRR
- Updated as new tests are completed
- Free download at woodworks.org

Value: Program

Level 1

Level 2





Concept Plan

Hillsboro Community Center at 53rd Ave.

opsis

Cost: Construction Type

TABLE 601Fire Resistance Rating Requirements for Building Elements (Hours)

Building Element	I-A	I-B	III-A		III-B	IV-A	IV-B	IV-C		IV-HT	V-A	V-B
Primary Structural Frame	3*	2*	1		0	3*	2	2		HT	1	0
Ext. Bearing Walls	3*	2*	2		2	3*	2	2		2	1	0
Int. Bearing Walls	3*	2*	1		0	3*	2	2		1/HT	1	0
Floor Construction	2	2*	1		0	2	2	2		HT	1	0
Roof Construction	1.5*	1*	1		0	1.5	1	1		HT	1	0
Exposed Mass Timber Elements						None	20-40%	Most		All		
		Baseline			+\$10/SF		+\$12-15/SF					
		0hr & HT			1hr & maybe 2hr		2hr FRR					
		$\geq \leq \geq$	\leq	\square]		\ge	\geq	\supset	< > <	1	
		\geq	$\leq > <$	\square]	>>>>	\times	\geq	\supset	$<\!\!>$	3	
]		\times	\geq	\mathbb{D}	<	3	
								\geq	\supset	<	Cost S	ource: Swinerton

*These values can be reduced based on certain conditions in IBC 403.2.1, which do not apply to Type IV buildings.

Cost Impacts of Construction Type

Construction Type Early Decision Example

3-story building on college campus

Mostly Group B occupancy, some assembly (events) space

- NFPA 13 sprinklers throughout
- Floor plate = 7,700 SF
- Total Building Area = 23,100 SF

Impact of Assembly Occupancy Placement:

Owner originally desires events space on top (3rd) floor

Requires Construction Type IIIA

If owner permits moving events space to 1st or 2nd floor

Could use Type IIIB

Cost Impacts of Construction Type

Construction Type Early Decision Example

3-story building on college campus

Cost Impact of Assembly Occupancy Placement:


Location of Event Space	3 rd Floor	1 st Floor
Construction Type	III-A	III-B
Assembly Group	A-3	A-3
Fire Resistive Rating	1-Hr	o-Hr
Connections	Concealed	Exposed
CLT Panel Thickness	5-Ply	3-Ply
Superstructure Cost/SF	<u>\$65/SF</u>	<u>\$53/SF</u>





Source: PCL Construction

Panel volume usually 65-80% of MT package volume




Source: Fast + Epp, Timber Bay Design Tool

Type IIIA option 1 1-hr FRR Purlin: 5.5"x28.5" Girder: 8.75"x33" Column: 10.5"x10.75" Floor panel: 5-ply

Glulam volume = 118 CF (22% of MT) CLT volume = 430 CF (78% of MT) Total volume = 0.73 CF / SF

Panel volume usually 65-80% of MT package volume




Source: Fast + Epp, Timber Bay Design Tool

Type IIIA option 2 1-hr FRR Purlin: 5.5"x24" Girder: 8.75"x33" Column: 10.5"x10.75" Floor panel: 5-ply

Glulam volume = 123 CF (22% of MT) CLT volume = 430 CF (78% of MT) Total volume = 0.74 CF / SF

Cost considerations: One additional beam (one additional erection pick), 2 more connections

Panel volume usually 65-80% of MT package volume




Source: Fast + Epp, Timber Bay Design Tool

Type IV-HT 0-hr FRR (min sizes per IBC) Purlin: 5.5"x24" (IBC min = 5"x10.5") Girder: 8.75"x33" (IBC min = 5"x10.5") Column: 10.5"x10.75" (IBC min = 6.75"x8.25") Floor panel: 3-ply (IBC min = 4" CLT)

Glulam volume = 120 CF (32% of MT) CLT volume = 258 CF (68% of MT) Total volume = 0.51 CF / SF

Which is the most efficient option?



Source: Fast + Epp, Timber Bay Design Tool

	Timber Volume Ratio
IIIA – Option 1	0.73 CF / SF
IIIA – Option 2	0.74 CF / SF
IV-HT	0.51 CF / SF

A general rule of thumb for efficient mass timber fiber volume is no higher than 0.75 CF per SF for up to a 1 hour rated structure (higher if 2 hour exposed timber in tall mass timber). Ratios in the 0.85 to 1.0 CF / SF range tend to become cost prohibitive





NOODWORKS

Gallery Why Wood? About

Need Project Support?



Key Design Considerations for Mass Timber Projects

Important considerations related to construction type, fire ratings, panel thickness, member size and occupancy.


Share 🞯

Selecting a Construction Type

For mass timber projects, selection of construction type is one of the more significant design decisions. While it's common to choose construction type based on structural material—i.e., to assume that steel and concrete structures should be Type II, light-frame wood should be Type V, and exposed heavy/mass timber should be Type IV—this approach can lead to additional costs. While Type IV construction can be used for exposed

Value: Open Floor Plan

Cost: Structural System & Grid



Baseline 12'-6" Glulam Spacing 5.5" CLT \$ +5% 15' Glulam Spacing 7" CLT

Source: Seattle Mass Timber Tower Book



Award Gallery

Why Wood? About

Need Project Support?



Expert Tips

Creating Efficient Structural Grids in Mass Timber Buildings

Although a mass timber solution may work economically on grids created for other materials, a few modifications can increase efficiencies related to member sizing and manufacturer capabilities.

Share 🞯

Mass timber products such as cross-laminated timber (CLT), nail-laminated timber (NLT) and glue-laminated timber (glulam) are at the core of a revolution that is shifting how designers think about construction. At no time has materials selection been such an integral aspect of the building designer's daily responsibilities. In addition to its sustainability and light carbon footprint, mass timber has benefits that include enhanced aesthetics, speed of construction and light weight, all of which can positively impact costs. However, to convince building owners and developers that a mass timber solution is viable, the structural design must also be cost competitive. This requires a full understanding of both material properties and



Perimeter Glazing

Value Analysis

$Value = \frac{function + faesthetics}{Cost}$




Value Analysis

$Value \ Engineering = \frac{Function + Aesthetics}{Cost}$



I HAR ST

Smaller grid bays at central core (more head height)
Main MEP trunk lines around core, smaller branches in exterior bays



Dropped below MT framing

- Can simplify coordination (fewer penetrations)
- Bigger impact on head height



In penetrations through MT framing

- Requires more coordination (penetrations)
- Bigger impact on structural capacity of penetrated members
- Minimal impact on head height



In chases above beams and below panels

- Fewer penetrations
- Bigger impact on head height (overall structure depth is greater)
- FRR impacts: top of beam exposure




- In gaps between MT panels
- Fewer penetrations, can allow for easier modifications later



In raised access floor (RAF) above MT

- Impact on head height
- Concealed space code provisions



In topping slab above MT

- Greater need for coordination prior to slab pour
- Limitations on what can be placed (thickness of topping slab)
- No opportunity for renovations later



Insurance Perspective on Mass Timber

- Lack of historic loss data = Unknowns
- Unknowns = Risk
- Risk = Higher Premiums
- Some take a 'wood is wood' approach
- Important to understand the significant differences in how mass timber performs in the event of a fire, etc. when compared to light wood-frame and all other building materials



Photo Credit: StructureCraft




Photo Credit: GLI Partners

Insurance vs. Building Codes

- It is important to note the distinct difference between the primary concerns of insurers vs. primary concerns of building codes
- Insurance primarily concerned with property loss
- Building codes primarily concerned with occupant safety
- As such, code acceptance and associated testing may be helpful to insurers in evaluating a new product like mass timber, but it will not address all concerns





Copyright Materials

This presentation is protected by US and International Copyright laws. Reproduction, distribution, display and use of the presentation without written permission of the speaker is prohibited.

© The Wood Products Council 2022

Funding provided in part by the Softwood Lumber Board

Disclaimer: The information in this presentation, including, without limitation, references to information contained in other publications or made available by other sources (collectively "information") should not be used or relied upon for any application without competent professional examination and verification of its accuracy, suitability, code compliance and applicability by a licensed engineer, architect or other professional. Neither the Wood Products Council nor its employees, consultants, nor any other individuals or entities who contributed to the information make any warranty, representative or guarantee, expressed or implied, that the information is suitable for any general or particular use, that it is compliant with applicable law, codes or ordinances, or that it is free from infringement of any patent(s), nor do they assume any legal liability or responsibility for the use, application of and/or reference to the information. Anyone making use of the information in any manner assumes all liability arising from such use.