

# Understanding Mass Timber and Cold-Formed Steel Hybrid Construction

Presented by:

**Hercend Mpidi Bita**

Principal  
Timber Engineering Inc.

**TIMBER** ENGINEERING

**Natalia Escobar**

Senior Designer/Manager  
Stantec Architecture



*Disclaimer: This presentation was developed by a third party and is not funded by WoodWorks or the Softwood Lumber Board.*

Bunker Hill Housing Redevelopment – Stellata  
/ Stantec / McNamara - Salvia / Leggat McCall  
Properties / Photo courtesy Stantec



## WoodWorks | The Wood Products Council

is a registered provider of AIA-approved continuing education under Provider Number G516. All registered **AIA CES** Providers must comply with the AIA Standards for Continuing Education Programs. Any questions or concerns about this provider or this learning program may be sent to AIA CES (cessupport@aia.org or (800) AIA 3837, Option 3).

This learning program is registered with **AIA CES** for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.

AIA continuing education credit has been reviewed and approved by **AIA CES**. Learners must complete the entire learning program to receive continuing education credit. AIA continuing education Learning Units earned upon completion of this course will be reported to **AIA CES** for AIA members. Certificates of Completion for both AIA members and non-AIA members are available upon request.

---

Questions related to specific materials, methods, and services will be addressed at the conclusion of this presentation.



# Course Description

---


This seminar explores the emerging hybrid construction method combining mass timber and cold-formed steel (CFS) to optimize structural performance and cost-effectiveness. We will examine structural, fire, and acoustic performance benefits, prefabrication advantages, and construction efficiencies. The presentation will also feature a detailed case study of the Bunker Hill Housing Redevelopment project in Boston, MA, showcasing a groundbreaking application of mass timber-CFS hybrid construction in an urban setting. Participants will gain insights into the design considerations, construction sequencing, benefits, and challenges associated with this hybrid structural system.

# Learning Objectives

---


1. Assess the structural efficiency, fire safety, acoustic performance, and sustainability advantages of integrating cross-laminated timber (CLT) and cold-formed steel (CFS) in mid-rise buildings.
2. Examine how the thermal performance of mass timber and cold-formed steel contributes to energy-efficient building envelopes and reduces operational carbon.
3. Compare the cost-effectiveness of CLT-CFS hybrid construction with conventional building systems, focusing on material efficiency, labor savings, and lifecycle costs.
4. Explain the gravity and lateral load-resisting strategies of mass timber and CFS hybrid systems, including platform-type construction and connection detailing.

# Wood Bearing Walls: WHEN ARE THEY VIABLE?




\*UP TO 60FT SHEAR WALLS NO SPLICE

# EFFICIENT SYSTEM






# EFFICIENT LOAD BEARING WALL LAYOUT



# LOADBEARING WALL SYSTEMS : PLATFORM TYPE


LOADBEARING LIGHTWOOD  
FRAMING  
 $\leq 5$  STOREYS



LOADBEARING CLT  
PLATFORM-TYPE  
UP TO 8-9 STOREYS




LOADBEARING CFS  
FRAMING  
UP TO 18 STOREYS







# EFFICIENT HYBRID SYSTEM FOR TALLWOOD– NEW APPROACH

UP TO 18 STOREYS




# EFFICIENT GRAVITY SYSTEM WHAT CREATES FORMS?


EFFICIENT STRUCTURAL LAYOUT  
PANEL UTILISATION AND EFFICIENCY  
TRANSPORTATION  
SITE CONSTRAINTS



# EFFICIENT LATERAL SYSTEM WHAT CREATES FORMS?



WOOD LLRS VIABLE UP TO~9 STOREY




HYBRID LLRS REQUIRED

# EFFICIENT LAYOUT – WHERE?

DIAPHRAGM  
CANTILEVER

**CONCRETE CORE/STEEL BRACES**



→ ELEVATION FLEXIBILITY

**SHEAR WALLS/BRACES**




→ PLAN LAYOUT FLEXIBILITY

# NEW APPROACH FOR TALL MID-RISE - MAC

CONCRETE PODIUM & CORE

PLATFORM TYPE CONSTRUCTION

- CFS LOAD BEARING WALLS
- CLT FLOOR PANELS



Credit – MA+HG ARCHITECTURE





# PROJECT TEAM

Owner	Tomo Spaces
Architectural	MA+HG
Consulting Arch	Eskew+Dumez+Ripple
Structural	Timber Engineering
CP/Code	GHL Consultants
Mechanical	Rocky Point Engineering
Fire Suppression	Rocky Point Engineering
Electrical	Nemetz (S/A) & Associates
Landscape	Hapa Collaborative
Envelope/Energy	Evoke Buildings
Civil	Creus Engineering
Geotech	Geopacific Consultants
Acoustic	BLK Consultants
Heritage	Donald Luxton &
Consultant	Associates, John Atkin
Indigenous	snəwəyət
Consultant	

Credit – MA+HG ARCHITECTURE



# EFFICIENT HEIGHT < 8-9 STOREYS

WALL SPACING – OPTIMISE LOADS ON WALLS

STUD SPACING – OPTIMISE LOADS ON STUDS

HEAVY STUDS AT LOWER LEVEL


VERTICAL MOVEMENTS ISSUES





C-Section




Back-to-Back C-Section




# INITIAL CONCEPTS – SCREW REINFORCEMENTS



# INITIAL CONCEPTS – DOWEL THROUGH CLT




**STEEL SPACERS** (credit Katerra/Mercer)




**HARDWOOD WOOD SPACERS**



# CONCRETE SPACERS





TOP VIEW




SECTION VIEW


# SIMPLICITY + REGULARITY = EFFICIENCY



# TRANSFER SLAB



# PROACTIVE ADAPTATION








# MODULAR TYPES FOR DIVERSE HOUSEHOLDS

 CFS Walls



# FIRE PERFORMANCE

2H FRR

12' SPAN – GRID SYSTEM

5PLY (175MM) V-GRADE CLT  
PANEL

DESIGN CHAR RATE  
0.65mm/MIN

ALTERNATIVE SOLUTION  
AVAILABLE TESTS AND  
LITERATURE



Credit – Katerra /Mercer

MAX. CLT SINGLE SPAN FOR 5PLY  
MULTI-SPAN WHERE POSSIBLE  
BREAK BETWEEN UNITS  
PANEL LAYOUT



# TALL MID-RISE – 5 TO 9 STOREYS

SPACERS vs NO SPACERS?


BACK TO BACK STUDS?

STUD SPACING?

SIZE OF CONCRETE SPACERS?

HSS POST/TRANSFER?

NUMBER OF TRADES?







# Incorporating Mass Timber in Hybrid Structures

Bunker Hill Housing Redevelopment – Stellata



# Development Vision

- To fast track the replacement of public housing units with pre-fabricated assemblies.
- To create a kit of parts model for sustainable urban design development.
- To be at the forefront of Sustainability with all buildings committed to Passive House prior to Energy Code updates.





# Masterplan Program

- Residential, retail and community uses
- 15 Residential Buildings
- Replacement of 1,010 existing public housing units with the addition of market rate units
- Total of 2,699 units
- 37% affordable unit ratio
- 7 acres of open space
- 50,000 SF of retail space





# Defining Design Targets

Rent-to-cost optimized product

- Limited unit, kitchen and bath types

Building forms and facades optimized for energy performance

- Early energy modeling to set design parameters

Structural system optimized for tall mid-rise (6-12+ stories)





# Phase 1: Stellata

- 6 Story Building
- 120,000 Gross SF
- 102 units – 100% affordable
- Passive House
- Construction type: 2021 IBC IV-C





# Partners

## Design Team



Copley  
Wolff

**Lam**  
Partners



ACENTECH



## Construction Team



## Passive House Team

• CPHC: **PE** Petersen Engineering


• CPHV: **RDH** BUILDING SCIENCE




JOSEPH J. CORCORAN  
COMPANY



# Component Construction



7-PLY CLT PLANKS












# Platform Framing

## Building Cumulative Shrinkage


- 1" for 6 stories
- Shrinkage would remain the same at the perimeter and the center across a floor. This would then be cumulative as each successive level goes up, but remain constant per level



# Edge of Slab Detail

Prefabricated exterior walls with cladding installed at the factory.  
Construction Tolerance becomes a Key!


7 ply CLT (62') gets hoist into place onto load bearing exterior and corridor walls.



# New Constructability Approach

AVB layer dual purpose:



- CLT Moisture protection
- Air and water seal at the exterior wall panels 4-joint





# New Constructability Approach


Tilt up panels with structure, sheathing, AVB, and cladding support installed.



# Deflection

Deflection bead at areas where demising wall met exposed CLT ceilings

App 5/8" deflection at floors and roof




# Acoustics

On the hunt for a tested assembly that will meet the project goals using 7-ply CLT


Lab Results:  
STC 55 / IIC 50

Field Test Results:  
STC: 57 / IIC: 49



# Fire Rating

- 2HR rated exterior walls: UL 425
- 2021 Type IV-C: Variance at the time of permitting



2

A-301

## BVS-1 - BRICK VENEER SYSTEM - (REV)

3" = 1'-0"



# Concealed Spaces

Combustible material protection required in concealed spaces under 2021 IBC Type IV-C

Taping and sealing of GWB joints, challenge with construction rain


## CONCEALED SPACES: TYPE IV-C

### Without Dropped Ceiling

Noncombustible material not required

Mass timber floor panel

Noncombustible protection not required




### With Dropped Ceiling

Noncombustible material not required

Mass timber floor panel

One layer 5/8" Type X gypsum\* covering all mass timber surfaces within concealed space

Dropped ceiling



# Challenge: Concealed Spaces



Combustible material protection  
required in concealed spaces  
under 2021 IBC Type IV-C





# Lessons Learned

- Connection of CLT to precast concrete walls.





# Lessons Learned

- Oversize door frame openings





# Lessons Learned

- Fastener heads, plates, stud packs
- Heavy studs for load bearing walls






# Lessons Learned

- L-Shape plate at top of exterior wall panel, exposed.



# Lessons Learned

- Exterior chord splice at panel joints at areas with exposed CLT.





# Benefits

## Decreased Construction Timeframe

- 7K SF floor structure per day
- 21K SF exterior walls in 6 days
- Building M beta test: 102 units, 16 months vs. 20+ mo.

## On-site Labor Force Efficiency

- Erection by 6-man carpentry crew
- 20%+ Reduction of Onsite Labor Hours

## Reduced Temporary Construction Items

- No construction hoist or operator – materials are preloaded during erection
- No exterior scaffolding – exterior walls glazed & finished
- No tower crane foundation
- Reduced winter weather mitigation





# Benefits

## CLT's single span across building

- Less crane picks – faster erection
- Maximizes fabrication efficiency

## CLT's light weight

- Lower foundation impact

## Fire Resistance





- Inherent 2HR fire resistance






# Design Flexibility

Average Unit Size: 914 SF

Unit Type		%	Unit Size
1 Bedroom		32%	600 - 650 SF
2 Bedroom		35%	750 - 920 SF
3 Bedroom		23%	980 - 1,060 SF
4 Bedroom		10%	1,300 - 1,320 SF



# Construction Progress









# Interior Design

BUNKER HILL HOUSING





# CLT Biophilia Effect

BUNKER HILL HOUSING



# QUESTIONS?

This concludes The American  
Institute of Architects Continuing  
Education Systems Course

**HERCEND MPIDI BITA**, Ph.D. P.Eng. P.E.  
Principal  
Timber Engineering Inc.  
400-19 East 5<sup>th</sup> Avenue  
Vancouver, BC V5T 1G7  
C +1 778 903 4553  
[hercend.mpidibita@timberengineering.ca](mailto:hercend.mpidibita@timberengineering.ca)

**NATALIA ESCOBAR**, AIA  
Senior Designer/Manager  
Stantec Architecture  
40 Water Street, 3<sup>rd</sup> floor  
Boston MA 02109  
C 407 451-6081  
[Natalia.Escobar@stantec.com](mailto:Natalia.Escobar@stantec.com)