



Designing and Building with Mass Timber:

Design, Planning and Performance


Presented By:
Jason Bahr, PE
October 5, 2023



Regional Directors: One-on-One Project Support



woodworks.org



Need Project
Support?



Building Systems

Light-Frame

Mass Timber / CLT

Off-Site / Panelized Construction

Hybrid

Building Types

Multi-Family / Mixed Use

Education

Office

Commercial Low-Rise

Industrial

Civic / Recreational

Institutional / Healthcare

[View All](#) ➔

On Demand Education

Find over 140 continuing education courses on wood topics for architects, engineers, general contractors, and code officials.

WoodWorks Innovation Network

Discover mass timber projects across the US and connect with their teams.

Our experts can help—ask us anything. [Get Free Project Support](#) ➔

WoodWorks is your go-to resource for commercial and multi-family wood building design, engineering, and construction. We're here to support you with free one-on-



[Learn](#)[Tools](#)[Events](#)[Award Gallery](#)[Why Wood?](#)[About](#)[Need Project Support?](#)

Building Systems

- ☐ Mass Timber / CLT 24
- ☐ Light-Frame 9
- ☐ Panelized Construction 7
- ☐ Hybrid 5

Building Types

- ☐ Multi-Family / Mixed-Use 16
- ☐ Education 10
- ☐ Office 10
- ☐ Commercial Low-Rise 9
- ☐ Civic / Recreational 6
- ☐ Industrial 6
- ☐ Institutional / Healthcare 6

Project Roles

- ☐ Architect 14
- ☐ Developer/Owner 11
- ☐ Structural Engineer 10
- ☐ Contractor/Installer 6

Resource Types

- ☐ Expert Tips 10
- ☐ Solution Papers 2
- ☐ Calculators 1
- ☐ Guides, Manuals & Inventories 1

Regions

- ☐ National 20
- ☐ Midwest 5
- ☐ South 4
- ☐ West 4



Acoustics and Mass Timber: Room-to-Room Noise Control

This paper covers key aspects of mass timber acoustical design, including rules of thumb for optimal design, common assemblies, detailing strategies, and flanking paths. Companion to the Inventory of Mass Timber Acoustic

Assemblies.

Solution Papers



Designing Mass Timber Floor Assemblies for Acoustics

The growing availability and code acceptance of mass timber for construction has given designers a low-carbon alternative.

Expert Tips



Impact of Wall Stud Size and Spacing on Fire and Acoustic Performance

Interior wall partitions in a wood-frame building—such as unit demising and corridor walls in a multi-family project—must meet several design objectives simultaneously. Two primary functions are fire resistance and acoustical separation. Having to cite two tested wall assemblies, one for fire-resistance endurance results and another for acoustic results, is common.

Expert Tips

Firehouse 12

The continuous plywood shell that creates varying acoustic conditions within the performance space forms the exterior of the auditorium.

Award Winner



Acoustical Considerations for Mixed-Use Wood-Frame Buildings

This paper will help you understand the effects of acoustics in the context of other performance areas, enabling you to more easily navigate the decisions and trade-offs required when evaluating assembly options.

Solution Papers




Holes and Penetrations in Mass Timber Floor and Roof Panels




Guidance for the design of mass timber floor and roof panels with openings, including structural, fire resistance, and acoustic impacts, and tips for reinforcement.

Expert Tips

woodworksinnovationnetwork.org



See innovative wood projects + their design teams.



Platte Fifteen

Denver, CO

OWNER
Crescent Real Estate LLC

ARCHITECT
OZ Architecture

STRUCTURAL ENGINEER
KL&A Engineers and Builders

CONTRACTOR
Adolfson & Peterson Construction

Who are you looking for?

Q Search by name or keyword...

Manufacturers Suppliers X

Hide Filters













Membership Type

Professionals Verified by Project Experience151	Companies Verified by Project Experience98
Community Members Verified by Education14	Manufacturers & Suppliers WoodWorks Partners22

Industry

- ☐ Architect 0
- ☐ Contractor 0
- ☐ Developer 0
- ☐ Engineer 0
- ☐ Installer 0
- ☐ Insurance Broker 0
- ☐ Other 0
- ☐ Structural Engineering 0

Companies and PROs

	StructureCraft Manufacturer Partner	 28	<div>View</div> <div>Save ↗</div>
	SmartLam NA Manufacturer Partner	 28	<div>View</div> <div>Save ↗</div>
	Sansin Manufacturer Partner	 23	<div>View</div> <div>Save ↗</div>
	Simpson Strong-Tie Manufacturer Partner	 22	<div>View</div> <div>Save ↗</div>
	DR Johnson Manufacturer Partner	 15	<div>View</div> <div>Save ↗</div>
	HASSLACHER Group	 14	<div>View</div>

Funding Partners



Forestry Innovation
Investment®



Sustaining Partners



Market Development Partners



Industry Advantage Partners




Channel Partners



presentation slides in pdf:

woodworks.org/presentation-archive/



Agenda



Designing and Building with Mass Timber: Design, Planning and Performance

11:00 -11:05 pm	Welcome and Introductions, Jason Bahr
11:05 – 12:05 pm	Designing and Building with Mass Timber: Design, Planning and Performance, pt.1
12:05 - 12:10 pm	Break
12:10 - 1:10 pm	Designing and Building with Mass Timber: Design, Planning and Performance, pt.2
1:10 - 1:30 pm	Q&A (optional)

“The Wood Products Council” is a Registered Provider with The American Institute of Architects Continuing Education Systems (AIA/CES), Provider #G516.

Credit(s) earned on completion of this course will be reported to **AIA CES** for AIA members. Certificates of Completion for both AIA members and non-AIA members are available upon request.

This course is registered with **AIA CES** for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.

Questions related to specific materials, methods, and services will be addressed at the conclusion of this presentation.



Course Description

How can architects, engineers and contractors collaborate to meet the growing demand for mass timber buildings? While developers across the country are pursuing mass timber projects, knowledge among AEC professionals is not yet widespread. Firms have varying degrees of familiarity with both the products and practicalities of designing, sourcing, and building a modern mass timber structure, and early adopters continue to play a significant role in educating the rest of the community. This presentation seeks to build on this openness and environment of shared learning, providing an overview of mass timber products, planning, design and implementation to maximize the benefits these buildings can deliver. We'll also discuss why some mass timber projects face resistance, and how to overcome misconceptions to achieve success. Topics will also include preconstruction coordination and interactions between the manufacturer and design/construction teams, case-based approaches to costing and scheduling, project delivery methods, how to achieve the highest level of efficiency for costs, schedule, and performance, and additional education and training opportunities.

Learning Objectives

1. Identify project planning, coordination and design topics that translate into successful buildings for both the design and construction team.
2. Explore best practices for interaction between manufacturer, design team and preconstruction manager that can lead to cost efficiency and safety on site.
3. Discuss potential construction schedule savings and construction fire safety practices realized through the use of prefabricated mass timber elements.
4. Discuss benefits of using mass timber products, including structural versatility, prefabrication, lighter carbon footprint, and reduced labor costs.

PRESENTATION OUTLINE

MASS TIMBER DESIGN

Products

Structural Solution & Connections

Projects and Code Considerations

MASS TIMBER CONSTRUCTION

Planning for Construction

Performing Construction

Workforce Development


MASS TIMBER OVERVIEW



Photo: PCL Construction

Current State of Mass Timber Projects

As of June 2023, in the US, **1,860** multi-family, commercial, or institutional projects have been constructed with, or are in design with, mass timber.




Scan this code or use the url to find the map and more details online.



www.woodworks.org/resources/mapping-mass-timber/

Current State of Mass Timber Projects

As of March 2022, in the US, **1,384** multi-family, commercial, or institutional projects have been constructed with, or are in design with, mass timber.



OVERVIEW | TIMBER METHODOLOGIES



Light Wood-Frame
Photo: WoodWorks



Heavy Timber
Photo: Benjamin Benschneider



Mass Timber
Photo: John Stamets

MASS TIMBER PRODUCTS



Glue Laminated Timber (Glulam)
Beams & columns



Cross-Laminated Timber (CLT)
Solid sawn laminations



Cross-Laminated Timber (CLT)
SCL laminations



Photo: Freres Lumber



Photo: StructureCraft



Photo: LendLease



Photo: LEVER Architecture

Dowel-Laminated Timber (DLT)



Photo: StructureCraft

Nail-Laminated Timber (NLT)



Photo: Think Wood

Glue-Laminated Timber (GLT)
Plank orientation



Photo: StructureCraft



Photo: StructureCraft



Photo: Ema Peter



Photo: Manasc Isaac
Architects/Fast + Epp

Glue Laminated Timber (GLT)






Photo: Manasc Isaac Architects/Fast + Epp

Cross-Laminated Timber (CLT)



Cross-Laminated Timber (CLT)

With solid sawn laminations



General Panel
thicknesses*
4 1/8" to 19 1/2"

General Panel
dimensions*
4 to 12 ft wide
24 to 64 ft long

*Consult with manufacturers for
available panel sizes

Cross-Laminated Timber (CLT)

With SCL laminations



Nail-Laminated Timber (NLT)




Photo: StructureCraft

Nail-Laminated Timber (NLT)



Photo: StructureCraft



Photo: Think Wood



Dowel-Laminated Timber (DLT)



Photo: StructureCraft

Other Mass Timber Product Options



Glue Laminated Timber
GLT



Laminated Veneer Lumber
LVL



Parallel Strand Lumber
PSL



Laminated Strand Lumber
LSL



Timber-Concrete Composite
TCC



Decking






Photo: Ema Peter

STRUCTURAL SOLUTIONS | POST, BEAM + PLATE



Photo: Seagate Structures

STRUCTURAL SOLUTIONS | POST + PLATE



Photo: Lendlease



Photo: John Klein

STRUCTURAL SOLUTIONS | HYBRID LIGHT-FRAME + MASS TIMBER



Photo: TimberLab

STRUCTURAL SOLUTIONS | HYBRID STEEL + MASS TIMBER



LEVER Architecture, photo Jeremy Bittermann


STRUCTURAL SOLUTIONS | HYBRID CONCRETE + MASS TIMBER

OVERVIEW | CONNECTIONS



Concealed Connectors

Photo Marcus Kauffman



Self Tapping Screws

Photo Simpson Strong Tie



OVERVIEW | CONNECTIONS



Beam to Column

Photo: StructureCraft



Photo: Structurlam



Column to Foundation

Photo: Alex Schreyer

OVERVIEW | CONNECTIONS



Panel to Panel & Supports

Photo: Charles Judd



Photo: Marcus Kauffman



Photos: Michael Elkan | Naturally Wood | UBC

PRECEDENT PROJECTS | BROCK COMMONS

INTRO, CLEVELAND

9 Stories | 115 ft
8 Timber Over 1 Podium

512,000 SF
297 Apartments, Mixed-Use

Photo: Harbor Bay Real Estate Advisors, Purple Film | Architect: Hartshorne Plunkard Architecture

INTRO, CLEVELAND

Type IV-B
Variance to expose ~50% ceilings

Photo: Harbor Bay Real Estate Advisors, Image Fiction | Architect: Hartshorne Plunkard Architecture



ASCENT, MILWAUKEE



Photo: Korb & Associates Architects |
Architect: Korb & Associates Architects



493,000 SF
259 APARTMENTS, MIXED-USE

ASCENT, MILWAUKEE

Tallest Mass Timber Building in the World



25 STORIES

19 TIMBER OVER 6 PODIUM, 284 FT



80 M ST, WASHINGTON, DC

3 STORY VERTICAL ADDITION
7 STORY EXISTING BUILDING

80 M ST, WASHINGTON, DC

100,000 SF

**2 NEW LEVELS OF CLASS A OFFICE SPACE
OCCUPIED PENTHOUSE
17'-0" CEILING HEIGHTS**



APEX PLAZA CHARLOTTESVILLE, VA

187,000 SF

Photo: WoodWorks | Architect: William McDonough + Partners

APEX PLAZA

CHARLOTTESVILLE, VA

8 STORIES

6 TIMBER OVER 2 PODIUM, 100 FT



PRIMARY OFFICE SPACE

11 E LENOX, BOSTON, MA

7 STORIES

70 FT

Passive House
Multi-Family




Credit: H + O Structural Engineering

Credit: Monte French Design Studio

11 E LENOX, BOSTON, MA



Credit: H + O Structural Engineering



Photos: StructureCraft



Photo: Hartshorne Plunkard Architecture

MASS TIMBER PROJECT CONSIDERATIONS



Photo: Hacker Architects


MASS TIMBER IN THE CODE




Photo: Freres Lumber

Mass Timber in Low- to Mid-Rise: 1-6 Stories in Construction Types III, IV or V


IBC Table 503: Base Height




IBC Section 504: NFPA 13-Compliant Sprinkler System




IBC Section 505: Mezzanine




IBC Section 510.2: Podium



Tall Mass Timber: Up to 18 Stories in Construction Types IV-A, IV-B or IV-C



Mass Timber’s Fire-Resistive Performance is Well-Tested, Documented and Recognized via Code Acceptance



Source: AWC’s TR 10

Table 16.2.1A Char Depth and Effective Char Depth (for $\beta_n = 1.5$ in./hr.)

Required Fire Resistance (hr.)	Char Depth, a_{char} (in.)	Effective Char Depth, a_{eff} (in.)
1-Hour	1.5	1.8
1½-Hour	2.1	2.5
2-Hour	2.6	3.2

Source: AWC’s NDS



Credit: David Barber, ARUP



Demonstrating Fire-Resistance Ratings for Mass Timber Elements in Tall Wood Structures

Changes to the 2021 International Building Code (IBC) have created opportunities for wood buildings that are much larger and taller than prescriptively allowed in past versions of the code. Occupant safety, and the need to ensure fire performance in particular, was a fundamental consideration as the changes were developed and approved. The result is three new construction types—Type IV-A, IV-B and IV-C—which are based on the previous Heavy Timber construction type (renamed Type IV-HT), but with additional fire protection requirements.

One of the main ways to demonstrate that a building will meet the required level of passive fire protection, regardless of structural materials, is through hourly fire-resistance ratings (FRRs) of its elements and assemblies. The IBC defines an FRR as the period of time a building element, component or assembly maintains the ability to confine a fire, continues to perform a given structural function, or both, as determined by the tests, or the methods based on tests, prescribed in Section 703.

FRRs for the new construction types are similar to those required for Type I construction, which is primarily steel and concrete.¹ (See Table 1.) They are found in IBC Table 601, which includes FRR requirements for all construction types and building elements; however, other code



- ## Mass Timber Fire Design Resource
- Code compliance options for demonstrating FRR
 - Updated as new tests are completed
 - Free download at woodworks.org

TABLE 1: FRR Requirements (Hours) for Tall Mass Timber Construction Types and Existing Type I

Building Element	I-A Unlimited stories, heights and areas*	IV-A Max. 19 stories, 270 ft, 324,000 sf**	I-B Max. 12 stories, 180 ft, unlimited areas*	IV-B Max. 12 stories, 180 ft, 216,000 sf**	IV-C Max. 9 stories, 85 ft, 135,000 sf**
Primary Frame	3	3	2	2	2
Exterior Bearing Walls	3	3	2	2	2
Interior Bearing Walls	3	3	2	2	2
Roof Construction	1.5	1.5	1	1	1
Primary Frame at Roof	2	2	1	1	1
Floor Construction	2	2	2	2	2

Assumes an NFPA 13 automatic sprinkler system throughout building

Source: 2021 IBC Tables 504.3, 504.4, 506.2 and 601

*Unlimited building size permitted for most occupancies

**Area limits indicated are per level, assuming no frontage increase; see IBC Tables 504.3, 504.4 and 506.2 for additional details

Cost: Construction Type

TABLE 601
Fire Resistance Rating Requirements for Building Elements (Hours)

Building Element	I-A	I-B	III-A	III-B	IV-A	IV-B	IV-C	IV-HT	V-A	V-B
Primary Structural Frame	3*	2*	1	0	3*	2	2	HT	1	0
Ext. Bearing Walls	3*	2*	2	2	3*	2	2	2	1	0
Int. Bearing Walls	3*	2*	1	0	3*	2	2	1/HT	1	0
Floor Construction	2	2*	1	0	2	2	2	HT	1	0
Roof Construction	1.5*	1*	1	0	1.5	1	1	HT	1	0


Exposed Mass Timber
Elements

None 20-40% Most All


Baseline
0hr & HT



+\$10/SF
1hr & maybe 2hr



+\$12-15/SF
2hr FRR



Cost Source: Swinerton

*These values can be reduced based on certain conditions in IBC 403.2.1, which do not apply to Type IV buildings.

Cost Impacts of Construction Type

Construction Type Early Decision Example



3-story building on college campus

- Mostly Group B occupancy, some assembly (events) space
- NFPA 13 sprinklers throughout
- Floor plate = 7,700 SF
- Total Building Area = 23,100 SF

Impact of Assembly Occupancy Placement:

Owner originally desires events space on top (3rd) floor

- Requires Construction **Type IIIA**

If owner permits moving events space to 1st or 2nd floor

- Could use **Type IIIB**

Cost Impacts of Construction Type

Construction Type Early Decision Example



3-story building on college campus

Cost Impact of Assembly Occupancy Placement:


Location of Event Space	3 rd Floor	1 st Floor
Construction Type	III-A	III-B
Assembly Group	A-3	A-3
Fire Resistive Rating	1-Hr	0-Hr
Connections	Concealed	Exposed
CLT Panel Thickness	5-Ply	3-Ply
<u>Superstructure Cost/SF</u>	<u>\$65/SF</u>	<u>\$53/SF</u>



Source: PCL Construction

Cost Implication of Design Choices

Panel volume usually 65-80% of MT package volume



Type IIIA option 1

1-hr FRR

Purlin: 5.5"x28.5"

Girder: 8.75"x33"

Column: 10.5"x10.75"

Floor panel: 5-ply

Glulam volume = 118 CF (22% of MT)


CLT volume = 430 CF (78% of MT)

Total volume = 0.73 CF / SF

Source: Fast + Epp, Timber Bay Design Tool

Cost Implication of Design Choices

Panel volume usually 65-80% of MT package volume



Source: Fast + Epp, Timber Bay Design Tool

Type IIIA option 2

1-hr FRR

Purlin: 5.5"x24"

Girder: 8.75"x33"

Column: 10.5"x10.75"

Floor panel: 5-ply

Glulam volume = 123 CF (22% of MT)


CLT volume = 430 CF (78% of MT)

Total volume = 0.74 CF / SF

Cost considerations: One additional beam (one additional erection pick), 2 more connections

Cost Implication of Design Choices

Panel volume usually 65-80% of MT package volume



Source: Fast + Epp, Timber Bay Design Tool

Type IV-HT

0-hr FRR (min sizes per IBC)

Purlin: 5.5"x24" (IBC min = 5"x10.5")

Girder: 8.75"x33" (IBC min = 5"x10.5")

Column: 10.5"x10.75" (IBC min = 6.75"x8.25")

Floor panel: 3-ply (IBC min = 4" CLT)


Glulam volume = 120 CF (32% of MT)

CLT volume = 258 CF (68% of MT)

Total volume = 0.51 CF / SF

Cost Implication of Design Choices

Which is the most efficient option?



Source: Fast + Epp, Timber Bay Design Tool

	Timber Volume Ratio
IIIA – Option 1	0.73 CF / SF
IIIA – Option 2	0.74 CF / SF
IV-HT	0.51 CF / SF

A general rule of thumb for efficient mass timber fiber volume is no higher than 0.75 CF per SF for up to a 1 hour rated structure (higher if 2 hour exposed timber in tall mass timber). Ratios in the 0.85 to 1.0 CF / SF range tend to become cost prohibitive

[Learn](#)[Tools](#)[Events](#)[Award Gallery](#)[Why Wood?](#)[About](#)[Need Project Support?](#)

Expert Tips

Key Design Considerations for Mass Timber Projects

Important considerations related to construction type, fire ratings, panel thickness, member size and occupancy.

Share

Selecting a Construction Type

For mass timber projects, selection of construction type is one of the more significant design decisions. While it's common to choose construction type based on structural material—i.e., to assume that steel and concrete structures should be Type II, light-frame wood should be Type V, and exposed heavy/mass timber should be Type IV—this approach can lead to additional costs. While Type IV construction can be used for exposed

[Learn](#)[Tools](#)[Events](#)[Award Gallery](#)[Why Wood?](#)[About](#)[Need Project Support?](#)

Expert Tips

Creating Efficient Structural Grids in Mass Timber Buildings

Although a mass timber solution may work economically on grids created for other materials, a few modifications can increase efficiencies related to member sizing and manufacturer capabilities.

Share

Mass timber products such as cross-laminated timber (CLT), nail-laminated timber (NLT) and glue-laminated timber (glulam) are at the core of a revolution that is shifting how designers think about construction. At no time has materials selection been such an integral aspect of the building designer's daily responsibilities. In addition to its sustainability and light carbon footprint, mass timber has benefits that include enhanced aesthetics, speed of construction and light weight, all of which can positively impact costs. However, to convince building owners and developers that a mass timber solution is viable, the structural design must also be cost competitive. This requires a full understanding of both material properties and

Value Analysis

$$\textit{Value} = \frac{\uparrow \textit{Function} + \uparrow \textit{Aesthetics}}{\downarrow \textit{Cost}}$$




Cost Impacts of Finish/ Appearance Grade

Appearance vs. Industrial Grades

Aesthetic Expectations

- Appearance grade more \$
- Industrial grade can save \$
- Specification of appearance grade varies by product
- CLT, DLT, NLT: aesthetic expectations are agreed upon by building designer and manufacturer/ fabricator (ask for samples & outline in specs)
- Glulam: grades are standardized



[Learn](#)[Tools](#)[Events](#)[Award Gallery](#)[Why Wood?](#)[About](#)[Need Project Support?](#)

Expert Tips

Specifying Appearance Grades for CLT, NLT and Glulam


Information for designers seeking to specify appearance grade for cross-laminated timber (CLT), nail-laminated timber (NLT), or glue-laminated timber (glulam).

Share 

For mass timber, specification of appearance grade varies by product. Aesthetic expectations for cross-laminated timber (CLT) and nail-laminated timber (NLT) are agreed upon between the building designer and manufacturer/fabricator and described in the product specifications, whereas grades for glued-laminated timber (glulam) are standardized.

CLT Appearance Grades

Starting with the 2015 version of the International Building Code (IBC), CLT has been prescriptively



J-Grade SPF



SPF Non-Visual

MASS TIMBER CONSTRUCTION MANAGEMENT

ANDY QUATTLEBAUM
OUTDOOR EDUCATION CENTER

Planning

- Anatomy of a Mass Timber Package
- Procurement, Supply Chain, Schedule Drivers

Environmental Exposure

- Site Planning
- Moisture Planning and Mitigation
- UV Planning and Mitigation

Workforce Training

- Strategic Partnerships
- Training/Education
- Resources

Holistic Costing




$\$/\text{SF}$




$\$/\text{SF}$

Image: GBD Architects

Anatomy of a Turnkey Mass Timber Package



Material (Direct Cost)




Turnkey Mass Timber Package



or




Mass Timber Package Costs



Panels are the biggest part of the biggest piece of the cost pie

Labor (Direct Cost)




Turnkey Mass Timber Package



Photo: Swinerton

Equipment (Direct Cost)



Turnkey Mass Timber Package

Source: Swinerton








Photo: Swinerton



Photo: Alex Schreyer

Project Overhead



Photos: Swinerton

Total Project Cost Analysis

CONSIDERATIONS:


- Ceiling Treatment
- Floor Topping
- HVAC System & Route
- Foundation Size
- Material Savings
- Perimeter glazing
- Value of Time
- Completion Bonds/Insurance



Sample Procurement Strategies

GC/CM Hires Turnkey Mass Timber Subcontractor	GC/CM Buys Material, Self-Performs Installation and Coordinates	GC/CM Buys Material, Subcontracts Labor and Coordinates
R I S K S P E C T R U M		
<ul style="list-style-type: none"> + Hiring experience + Single point of responsibility 	<ul style="list-style-type: none"> + Hiring experience + Single point of responsibility + Financial security of strong GC/CM 	<ul style="list-style-type: none"> + Potential added mark-up
<ul style="list-style-type: none"> – Prequalify capacity of subs – Potential added mark-up 	<ul style="list-style-type: none"> – Lack of familiarity with supply chain – Steep learning curve for coordination 	<ul style="list-style-type: none"> – Multiple layers of coordination – Prequalify capacity of sub

Potential Cost Impacts: Design-Bid-Build Procurement







Alternate Procurement Option: Trade Partner/Master Builder Approach



Understand the Supply Chain




Photo: Swinerton




Credit: Tanya Luthi, Entuitive

Understand Manufacturer's Capabilities

Understand Manufacturer's Capabilities




Credit: TimberLab



Embrace the
Prefab Advantage

Tolerances: Interface with Other Structural Materials



Photos: Swinerton


Schedule Drivers



Procurement Approach Determines Schedule

Compressing the Typical Construction Schedule with Mass Timber ^{13, 15, 16}

Look for these potential schedule savings in comparison to steel and concrete




Up to 25% schedule savings

- = Less carrying costs
- + Less GC overhead
- + Ability to lease/occupy sooner

Procurement Approach Determines Schedule

Example 6 Story Type IIIA Project




Source: Swinerton

Design-Bid-Build Procurement

Procurement Approach Determines Schedule

Example 6 Story Type IIIA Project



Source: Swinerton

Design-Build/Design-Assist Procurement

Schedule Comparison




Image: Swinerton




Photo: WoodWorks

Schedule Impacts: Hybrid Structures




Early Move-In for Rough-In Trades.



Photos: Swinerton



Embracing BIM for Fabrication



Photos: Swinerton


MEP Layout & Integration



MEP Layout & Integration

Smaller grid bays at central core (more head height)

- Main MEP trunk lines around core, smaller branches in exterior bays



Credit: Blaine Brownell



Credit: WoodWorks

MEP Layout & Integration

Dropped below MT framing

- Can simplify coordination (fewer penetrations)
- Bigger impact on head height



MEP Layout & Integration

In penetrations through MT framing

- Requires more coordination (penetrations)
- Bigger impact on structural capacity of penetrated members
- Minimal impact on head height



Credit: WoodWorks



Credit: WoodWorks

MEP Layout & Integration

In chases above beams and below panels

- Fewer penetrations
- Bigger impact on head height (overall structure depth is greater)
- FRR impacts: top of beam exposure



Credit: JC Buck



Credit: KL&A Engineers & Builders

MEP Layout & Integration

In gaps between MT panels

- Fewer penetrations, can allow for easier modifications later



Credit: Ema Peter/MGA




Credit: Hacker Architects

MEP Layout & Integration

In raised access floor (RAF) above MT

- Impact on head height
- Concealed space code provisions



Credit: Global IFS



MEP Layout & Integration

In topping slab above MT

- Greater need for coordination prior to slab pour
- Limitations on what can be placed (thickness of topping slab)
- No opportunity for renovations later



SITE PLANNING



QA/QC



Photo: Swinerton

SITE INSPECTIONS



Photo: H+O Structural Engineering, Kure Creative

Tall Mass Timber Special Inspections

TABLE 1705.5.3
REQUIRED SPECIAL INSPECTIONS OF MASS TIMBER CONSTRUCTION

<u>Type</u>	<u>Continuous Special Inspection</u>	<u>Periodic Special Inspection</u>
<u>1. Inspection of anchorage and connections of mass timber construction to timber deep foundation systems.</u>		<u>X</u>
<u>2. Inspect erection of mass timber construction</u>		<u>X</u>
<u>3. Inspection of connections where installation methods are required to meet design loads</u>		
<u>3.1. Threaded fasteners</u>		
<u>3.1.1. Verify use of proper installation equipment.</u>		<u>X</u>
<u>3.1.2. Verify use of pre-drilled holes where required.</u>		<u>X</u>
<u>3.1.3. Inspect screws, including diameter, length, head type, spacing, installation angle, and depth.</u>		<u>X</u>
<u>3.2. Adhesive anchors installed in horizontal or upwardly inclined orientation to resist sustained tension loads</u>	<u>X</u>	
<u>3.3. Adhesive anchors not defined in 3.2.</u>		<u>X</u>
<u>3.4. Bolted connections</u>		<u>X</u>
<u>3.5. Concealed connections</u>		<u>X</u>

PICK PLAN



Photo: Swinerton

MATERIAL DELIVERY



Photo: Swinerton



STAGING

Photo: Swinerton

Planning for Environmental Exposures




- Plan Early
- Risk Evaluation
- Develop Construction Phase Plan
- Execute the Design and Moisture Management Plan
- Monitor

RDH Moisture
Management Guide 1st Ed



Onsite Considerations



Other Materials



Workforce Development

Training is the key to efficiency
Training takes time and money

Training versus Education

Resources available to all

MT Construction Manual
Installer Curriculum
Other WW Resources
CM Workshops
Previous recorded versions
Learning Management System

Mass Timber Construction Management Program



MASS TIMBER CONSTRUCTION
MANUAL



8- & 16-HOUR INSTALLER
TRAINING PACKAGE AND
TRAINING CENTERS



COMMUNITY COLLEGE
AND UNIVERSITY CM
PROGRAMS



VIRTUAL AND/OR IN-PERSON
WORKSHOPS



PARTNER WITH
CONSTRUCTION ASSOCIATIONS



PROJECT TOURS




ENGAGE WITH GENERAL
CONTRACTORS ACROSS THE US



Released on 20 October 2021

<https://www.woodworks.org/mass-timber-construction-management-program/>





Designing a wood building? Ask us anything.

| FREE PROJECT SUPPORT / EDUCATION / RESOURCES

Nationwide support for the code-compliant design, engineering and construction of non-residential and multi-family wood buildings.

- Allowable Heights/Areas
- Construction Types
- Structural Detailing
- Wood-Framed & Hybrid Systems
- Fire/Acoustic Assemblies
- Lateral System Design
- Alternate Means of Compliance
- Energy-Efficient Detailing
- Building Systems & Technologies

| woodworks.org/project-assistance | help@woodworks.org



John W. Olver Design Building at UMass Amherst
Leers Weinzapfel Associates, Equilibrium Consulting
photo © Albert Vecerka / Esto

Questions? Ask us anything.



Jason Bahr, PE
Regional Director | KS, AR, MO, OK
(913) 732-0075
jason.bahr@woodworks.org



Please take our survey!



Copyright Materials

This presentation is protected by US
and International Copyright laws.

Reproduction, distribution, display and use of
the presentation without written permission
of the speaker is prohibited.

© The Wood Products Council 2022

Funding provided in part by the Softwood Lumber Board

Disclaimer: The information in this presentation, including, without limitation, references to information contained in other publications or made available by other sources (collectively “information”) should not be used or relied upon for any application without competent professional examination and verification of its accuracy, suitability, code compliance and applicability by a licensed engineer, architect or other professional. Neither the Wood Products Council nor its employees, consultants, nor any other individuals or entities who contributed to the information make any warranty, representative or guarantee, expressed or implied, that the information is suitable for any general or particular use, that it is compliant with applicable law, codes or ordinances, or that it is free from infringement of any patent(s), nor do they assume any legal liability or responsibility for the use, application of and/or reference to the information. Anyone making use of the information in any manner assumes all liability arising from such use.