

MASS TIMBER COMPARATIVE LIFE CYCLE ASSESSMENT SERIES


COMPARING THE EMBODIED CARBON IMPACTS AND COST OF MASS
TIMBER BUILDINGS TO FUNCTIONALLY EQUIVALENT BUILDINGS

Alexis Feitel, P.E.
Team Carbon Unit Director & Structural Engineer afeitel@klaa.com


Anli Ni
Structural Designer & Embodied Carbon Specialist ani@klaa.com

Disclaimer: This presentation was developed by a third party and is not funded by WoodWorks or the Softwood Lumber Board.

Photo Credit: JC Buck



**WoodWorks, KL&A Team Carbon,
USDA U.S. Forest Service, Softwood Lumber Board**



Return to Form



Multifamily / Retail

Type IV-B Construction

139,000 ft² (12,900 m²)

12 Story

Denver, CO



Nez Perce USFS


Office

Type V-B Construction

16,045 ft² (1,491 m²)

2 Story

Kamiah, ID



Burwell Center

Office / Higher Ed

Type III-B Construction

22,990 ft² (2,136 m²)

3 Story

Denver, CO



Denver Office


Office / Higher Ed


Type III-A Construction

98,280 ft² (9,130 m²)

4 Story


Denver, CO



- 
- **Building Study Methodology**
 - **Building Study Results (GWP/m² & Cost)**
 - Denver Office Building (4 Story Office/Higher Ed)
 - Return to Form (12 Story Multifamily)
 - Nez Perce-Clearwater National Forests Office (2 Story Office)
 - Burwell Center for Career Achievement (3 Story Office/Higher Ed)
 - ★ • **Building Study Trends (GWP/m² & Cost)** ★


OUTLINE

- **Comparative WBLCA**

- TallyLCA 
- Scope
 - Structure
 - Enclosure – Vertical and Horizontal
 - Fire Resistance
 - Acoustic
 - Ceiling Finishes
- Cradle-to-Grave (A-C, plus Module D)
- Includes Biogenic Carbon (-1/+1, 32% Permanent Storage)
- Data: Methodology, Assumptions, End-of-Life, Uncertainty

- **Comparative Cost & Speed of Construction**

- Normalized Material & Labor Costs




BUILDING STUDY METHODOLOGY

Photo by Aleksandar Radovanovic on Unsplash

- **Comparative Design**

- Functionally Equivalent (ISO 14044 4.2.3.7 & ASTM E2921)
- Construction Type
 - Fire Resistance Rating
- Design Efficiencies & Considerations
 - Framing Scheme
 - Span Lengths
 - Grid Layout → Eliminate Transfer Podiums
 - Floor Assembly Thicknesses → Building Height
 - Building Weight → Foundations, Lateral System
 - Acoustic Assembly
 - Ceiling Assembly



BUILDING STUDY METHODOLOGY

Photo by Aleksandar Radovanovic on Unsplash




CRADLE TO GRAVE + MODULE D

CRADLE TO GRAVE

CRADLE TO GATE

Production			Construction		Use							End-of-Life				Module D		
A1	A2	A3	A4	A5	B1	B2	B3	B4	B5	B6	B7	C1	C2	C3	C4	D1	D2	D3
Raw Material Supply	Transportation	Manufacturing	Transportation	Construction/Installation	Use	Maintenance	Repair	Replacement	Refurbishment	Operational Energy Use	Operational Water Use	Deconstruction/Demolition	Transportation	Waste Processing	Disposal	Reuse	Recycling	Energy Recovery

Note that the stages and information modules shown here deviate slightly from the naming convention used in ISO 21930. However, this series generally uses terminology consistent with ISO 21930.



Sustainable Sourcing

- ISO 21930 7.2.11

+1/-1 Static Accounting

- ISO 21930 7.2.7

TallyLCA EOL Allocation



- 32% Permanently Stored

Material	Incineration	Landfill	Recycling / Recovery	Accounting Method
Concrete		45%	55%	Recycled into aggregate, credited for avoided burden of production of aggregate, considers impact of grinding energy
Steel & Reinforcement		2%	98%	Recycled virgin material is credited for avoided burden of production (net scrap), considers processing impacts
Mass Timber	22%	63.5%	14.5%	Incineration is credited for energy recovery, landfill considers 50% decomposition and release of biogenic carbon (with credit for energy recovery due to landfill gas capture) and 50% is permanently stored, recycling is credited as avoided burden, considers impact of grinding energy
Glass		100%		
Gypsum Board		100%		
Plastic		100%		
Insulation		100%		

Image by WoodWorks

BIOGENIC CARBON METHODOLOGY

Photo by Aleksandar Radovanovic on Unsplash

Office / Higher Education
Type III-A Construction
98,280 ft² (9,130 m²)
4 Story

Architect: Shears Adkins Rockmore
Engineer: KL&A
Contractor: PCL


Foundations: Spread Footings
No below grade

L1: Concrete Slab on Grade

L2 – Roof: CLT Panel & Glulam


Lateral: Precast Concrete Core Walls + Glulam Brace

Grid: 20' X 34'




Denver Office Building


Denver, Colorado




- FLOOR: 5ply CLT Floor, Concrete Topping Slab, Glulam Framing
- ROOF: 5ply CLT, Glulam Framing
- LATERAL: Precast Concrete Walls, Glulam Brace



MASS TIMBER
(AS DESIGNED)




- FLOOR: Concrete on Metal Deck, WF Framing
- ROOF: Metal Deck, WF Framing
- LATERAL: Precast Concrete Walls, Steel Brace



STEEL

FUNCTIONAL EQUIVALENCY

Denver Office Building






Goal: Design & Component Specifications to achieve Functional Equivalency

- Construction Type
 - Fire Resistance Rating
- Design Efficiencies & Considerations
 - Framing Scheme
 - Span Lengths
 - Grid Layout
 - Floor Assembly Thicknesses → Building Height
 - Building Weight → Foundations, Lateral System
 - Acoustic Assembly
 - Ceiling Assembly
- Component Specifications

Floor Elevations and Building Height			
Structural System	Floor-to-Floor Height	Floor to Ceiling*	Total Building Height
Mass Timber	13'-4"	10'-3"	63'-7"
Steel	14'-0"	10'-0"	65'-7"

Concrete Mix Property Assumptions	
Element	Concrete (psi, SCM%)
SOG	4000, 20% FA
Columns	5000, 20% FA
Pilasters	5000, 40% FA
Mat Slabs	5000, 40% FA
Footings	5000, 40% FA
Foundation Walls	5000, 40% FA
Precast Shear Walls	6000, 40% FA
Slab on Metal Deck	4000, 20% FA
Topping Slabs	4000, 20% FA





FUNCTIONAL EQUIVALENCY

DENVER OFFICE



Steel Typical Floor Plan







**42% TOTAL
REDUCTION**

**32% ARCH
REDUCTION**

**46% STRUCTURAL
REDUCTION**


Mass timber material
contributes 0.5% to
superstructure GWP

Total Building GWP




DENVER OFFICE – TOTAL GWP

3,940 km (2,450 miles)




Total Building GWP per Life Cycle Stage



Mix Assumptions for Wood:

32% Permanently Stored

- 63.5% Landfill
- 22.0% Incineration
- 14.5% Recycle




A4 GWP = 35% of
Stored Biogenic
Carbon

■ Mass Timber
■ Steel





DENVER OFFICE – LCA STAGES




-256 kgCO₂eq/m²
vs
140-239 kgCO₂eq/m²

Stored Biogenic Carbon GWP




DENVER OFFICE – BIOGENIC CARBON



2.5 Months Faster

0% \$ Premium

Construction Cost



DENVER OFFICE – COST & SCHEDULE

Return To Form

Comparative Life Cycle Assessment Study

Author: KL&A Engineers & Builders




Image by WoodWorks

Multifamily / Retail

Type IV-B Construction, IBC 2018 with Denver Amendments (2024 IBC)

139,000 ft² (12,900 m²)

12 Story

Foundations: Drilled Piers

No below grade

L1: Concrete Slab on Grade

L2-L4: Concrete Slabs

L5 - Roof: CLT Panel & Glulam

Lateral: Concrete Cores


Grid: 20' x 20'

Owner: Katz Development

Architect: tres birds







Engineer: KL&A

Contractor: Swinerton



RETURN TO FORM




Denver, Colorado



MASS TIMBER
(AS DESIGNED)
Type IV-B

STEEL "CFS"
(CFS & DECK)
Type I-B


CONCRETE
(PT)
Type I-B



Concrete Volume:


MT 23% Reduction
CFS 11% Reduction

Building GWP is
dominated by Concrete
at Level 4 Podium
& Below





“Above Podium”
(GWP/m²)

= Above Podium GWP /
Above Podium Floor Area




MT < CFS < CONC
21%-25%
REDUCTION

Total Building GWP: System and Material Contributions




RTF – TOTAL GWP




MT < CFS < CONC
73%-83%
REDUCTION

Above-Podium Structural GWP




RTF – STRUCTURE ABOVE PODIUM



~20% Foundation
Impact

Structural Substructure and Superstructure GWP



RTF – SUBSTRUCTURE vs SUPERSTRUCTURE

NEZ PERCE-CLEARWATER NATIONAL FORESTS SUPERVISOR'S OFFICE KAMIAH, ID

Office

Type V-B Construction

16,045 ft² (1,491 m²)

2 Story

Foundations: Spread Footings

Partial Below Grade



L1: Concrete Slab on Grade

L2: Partial, Light Frame Wood & MT Hybrid

Roof: CLT Panel & Glulam

Lateral: Light Frame Wood Shear Walls


CLT Elevator Walls



Owner: U.S. Forest Service
Architect: Mosaic Architecture
Engineer: Morrison-Maierle
Contractor: Quality Contractors



MASS TIMBER – LIGHT FRAME HYBRID (AS CONSTRUCTED, 2021)




STEEL




- FLOOR: Plywood Sheathing, I-Joists, Glulam Beams
(No Topping Slab)
- ROOF: 4ply CLT, Glulam Beams & Columns
- WALLS: Light Frame Wood Walls & CLT Elevator Walls

- FLOOR: Concrete on Metal Deck, WF Beams
- ROOF: Metal Deck, Steel Bar Joists, WF Beams
- WALLS: CFS Stud Walls & CMU Elevator Walls




MT < STEEL
43% REDUCTION

Total Building GWP – System and Material Contributions





NP – TOTAL GWP



**69% SUPERSTRUCTURE
REDUCTION**

**118% STRUCTURAL
REDUCTION**

Superstructure Structural GWP




- Wood
- Metals
- Concrete
- Masonry

NP – SUPERSTRUCTURE GWP

Office / Higher Education
Type III-B Construction
22,990 ft² (2,136 m²)
3 Story


Foundations: Drilled Piers
No below grade
L1: Concrete Slab on Grade
L2 – Roof: CLT Panel & Glulam
Lateral: CLT Panel Walls at Core
Grid: 11' X 24'

Owner: University of Denver
Architect: Lake Flato, Shears Adkins Rockmore
Engineer: KL&A
Contractor: PCL





Burwell Center for Career Achievement

Denver, Colorado





MASS TIMBER (AS CONSTRUCTED, 2020)

- FLOOR: 3ply CLT Floor, Concrete Topping Slab, Glulam Framing
- ROOF: 3ply CLT, Glulam Framing
- LATERAL: 5ply CLT Core Walls



STEEL

- FLOOR: Concrete on Metal Deck, WF Framing
- ROOF: Metal Deck, WF Framing
- LATERAL: CMU Core Walls & Steel Brace





MT < STEEL
31% TOTAL REDUCTION


SUPERSTRUCTURE
40% REDUCTION

SUPERSTRUCTURE
STRUCTURE
79% REDUCTION

Total Building GWP – System and Material Contributions





BURWELL – TOTAL GWP



MT < STEEL
98% REDUCTION


Lateral System Component Contributions



- CLT
- Steel Plate
- CMU with Mortar & Grout
- Steel Reinforcement
- Steel Brace




BURWELL – LATERAL SYSTEM



STUDY TRENDS





Return to Form


Multifamily / Retail

Type IV-B Construction

139,000 ft² (12,900 m²)

12 Story

Denver, CO



Nez Perce USFS


Office

Type V-B Construction

16,045 ft² (1,491 m²)

2 Story

Kamiah, ID



Burwell Center

Office / Higher Ed

Type III-B Construction

22,990 ft² (2,136 m²)

3 Story

Denver, CO



Denver Office


Office / Higher Ed

Type III-A Construction


98,280 ft² (9,130 m²)

4 Story

Denver, CO






Total Building GWP



21% – 43%
Reduction

TOTAL BUILDING TRENDS

COMPARATIVE STUDY SERIES



**Return to
Form – Steel**



**Return to
Form –
Concrete**



Nez Perce



Burwell



**Denver Office
Building**




 = about 10 homes;  = about 10 cars

EQUIVALENT TRENDS

COMPARATIVE STUDY SERIES

Range of GWP Reductions by System



SYSTEM TRENDS

COMPARATIVE STUDY SERIES

GWP Comparisons Showing System and Material Breakdowns

Total Building


21% – 43%
Reduction

Total Structure

24% – 55%
Reduction

Superstructure Structure


63% – 118%
Reduction



SYSTEM TRENDS

COMPARATIVE STUDY SERIES

Superstructure/Above-Podium Structural Material GWP



63% – 118%
Reduction

SUPERSTRUCTURE STRUCTURAL TRENDS

COMPARATIVE STUDY SERIES

-165 to -256 kgCO₂/m²

Stored Biogenic Carbon

Equivalent to


221,700 ft² (20,600 m²)
New Construction

Equivalent to

1135+ Flights, Roundtrip
Denver to London

16 Minutes

Regrow the Wood of All 4
Buildings



BIOGENIC CARBON TRENDS

COMPARATIVE STUDY SERIES

Structure Raw Material

8 – 126% Premium

Structure Construction



3 – 16% Premium

Whole Building Construction


0 – 6% Premium

Schedule

16% Average Savings




Relative Cost Premiums



COST TRENDS

COMPARATIVE STUDY SERIES


Comparative GWP, Cost, and Schedule



TOTAL BUILDING TRENDS

COMPARATIVE STUDY SERIES

Comparative GWP, Cost, and Schedule



TOTAL BUILDING TRENDS

COMPARATIVE STUDY SERIES

- MASS TIMBER STRUCTURAL SYSTEMS HAVE CLEAR EMBODIED CARBON BENEFITS (SOURCE RESPONSIBLY & STAY INFORMED)
- GWP vs COST BALANCE
- SPEED OF CONSTRUCTION
- RESPECT STORED BIOGENIC CARBON
- DESIGN FOR DECONSTRUCTION & EASY RECOVERY
- EMBODIED CARBON AT CONCEPT DESIGN




Photo Credit: JC Buck

This concludes The American Institute of Architects Continuing Education Systems Course.


THANK YOU



KL&A
Engineers & Builders

Alexis Feitel, P.E.
afeitel@klaa.com

Anli Ni
ani@klaa.com



Credit: Feitel