

Orchards at Orenco: Phase I vs. Phase II

# More Units...Less Cost...Still Passive

Michael Bonn  
Ankrom Moisan Architects

Woodworks  
March 2022



*Disclaimer: This presentation was developed by a third party and is not funded by WoodWorks or the Softwood Lumber Board.*

# Outline

- Orchards at Orenco – Background & Context
- Orchards Ph. I vs. Orchards Ph. II
  - Design
  - Passive House Process
  - Construction
  - Feedback / Monitoring / Measured Performance
  - Challenges and Lessons Learned
  - Costs
- Orchards at Orenco – Proof of Concept?

# Learning Objectives

- Demonstrate how the Passive House standard has been applied successfully to affordable housing development, serving as a model for future developments in North America, and serving as a primary path to achieving net zero energy affordable housing
- Describe the key design measures incorporated in the overall building design, enclosure and mechanical systems to achieve Passive House certification
- Describe the integrated teamwork / process used by the project team in the design, construction and operation of high performance affordable housing
- Demonstrate how efficient design and cost optimization can be used to reduce the overall development and operating costs of affordable housing

# The Orchards at Orenco

- Affordable housing community in Hillsboro, OR
  - Phase I: 57 units of workforce housing  
(completed 6/2015)
  - Phase II: 58 units of workforce housing  
(completed 7/2016)
  - Phase III: 52 units of family sized workforce housing  
(completed 2018)
- Developer/Owner:  
REACH Community Development

# REACH Community Development


- REACH's goal is to provide **Healthy, Safe and Affordable** living
- Affordability not only includes low rents but also close proximity to work and schools, and low **monthly utility bills**
- REACH set a goal in their 2010 Strategic Plan to have a Passive House project in their portfolio by 2015

# Why Passive House?


- Most rigorous building energy efficiency standard in world
- Achieve significant reductions of utility costs to residents, while improving comfort and durability
- The right path to net zero...

# Orchards at Orenco - Background

- Site history
- Suburban location
- Growing community
- High-tech employer base
- Light rail TOD







# The Orchards at Orenco

REACH COMMUNITY DEVELOPMENT

ANKROM MOISAN ARCHITECTS

WALSH CONSTRUCTION CO.



# Phase I Basics

- 57 units of affordable workforce housing
- 57,750 square feet
- 3-story, wood frame construction on concrete slab-on-grade foundation




# Design Overview

Photo Credit: Casey Braunger






## Aerial View from South




# First Floor Plan






### Typical Roof Assembly: R-81

- 80 mil TPO roof membrane (fully adhered, white)
- 1/2" coverboard
- 12" polyisocyanurate insulation
- Self-adhered rubberized asphalt membrane vapor barrier (serves also as temp. roof)
- 3/4" plywood
- Prefabricated wood truss framing (trusses @ 24" o.c.)
- 5/8" gypsum wall board (2 layers)



### Typical Exterior Wall Assembly: R-39

- Fiber cement siding w/ treated 1x wood furring @ 24" o.c.
- 1-1/2" rigid mineral wool insulation (8 lb. density)
- Spun-bonded polyolefin sheet water-resistive barrier
- 1/2" plywood with air sealing tape at all seams
- 2x10 wood framing (studs at 24" o.c.)
- 9 1/4" blown fiberglass insulation at all framing cavities
- Polyamide sheet vapor barrier
- 5/8" gypsum wall board



### Typical Slab Assembly: R-19

- 4" concrete slab
- 15 mil polymer sheet vapor barrier
- 4" Type II expanded polystyrene insulation
- Gravel base with radon mitigation system piping

# Enclosure Assemblies

# HVAC Design






A photograph of a mechanical penthouse interior. The space is filled with stainless steel equipment, including large rectangular units and a sloped structure on the left. Black pipes and conduits run across the ceiling and walls. A wooden floor is visible in the foreground, and a fluorescent light fixture is mounted on the ceiling.

# Mechanical Penthouse



# HVAC Design



- 3 HRV Zones
- Cook ERV serves each zone

# HVAC Design

- Continuous 50cfm supply air per bedroom
- Continuous exhaust at kitchen and bath
- Electric cove heater in living room for user control & backup heat
  - Estimated at 20% of building heating load
- No active cooling at apartments




Image courtesy of PAE Consulting Engineers













REACH COMMUNITY DEVELOPMENT



ANKROM MOISAN ARCHITECTS



WALSH CONSTRUCTION CO.













REACH COMMUNITY DEVELOPMENT




ANKROM MOISAN ARCHITECTS




WALSH CONSTRUCTION CO.








**Preliminary Airtightness Test Result: 0.0875 ACH<sub>50</sub>**







**Final Airtightness Test Result: 0.133 ACH<sub>50</sub>**

# Phase I - Lessons Learned

- Owner vision - and commitment - is pivotal

# Phase I - Lessons Learned

- Owner vision - and commitment - is pivotal
- It takes a team...working collaboratively, with everyone pulling in the same direction





# Phase I - Lessons Learned

- Owner vision - and commitment - is pivotal
- It takes a team...working collaboratively, with everyone pulling in the same direction
- Early team integration pays off

# Phase I - Lessons Learned

- Owner vision - and commitment - is pivotal
- It takes a team...working collaboratively, with everyone pulling in the same direction
- Early team integration pays off
- Proactive coordination and QC is essential

# Phase I - Lessons Learned

- Owner vision - and commitment - is pivotal
- It takes a team...working collaboratively, with everyone pulling in the same direction
- Early team integration pays off
- Proactive coordination and QC is essential
- Keep it simple





Photo Credit: Casey Braunger






Photo Credit: Casey Braunger




Photo Credit: Casey Braunger



# Measured Performance


## Orchards Phase I Energy Use: Measured vs Modeled (PHPP)



Graph courtesy of REACH Community Development / Housing Development Center

# Measured Performance

- Apartments energy use lower than modeled
- Common area electricity use much higher than modeled
  - Causes have been investigated
  - Fan at 3<sup>rd</sup> floor storage room that should be on timer is running continuously
  - Elevator usage higher than anticipated
  - Thermostats at freeze protection heaters in stairwells had been set at 70 degrees, have now been set to 45 degrees
  - DAS system added late during construction was not in original model (increasing site EUI slightly: approx. 0.2 kBtu/sf/yr)



# Cost Premium & Financing

## Uses

Incremental Soft Costs	\$	148,580
Incremental Hard Costs	\$	910,520
Total incremental Cost	\$	1,059,100
Premium over "typical Orenco"		11.0%

## Sources

REACH Equity	\$	300,000
Meyer Memorial Trust grant	\$	500,000
Neighborworks grant	\$	260,000
OHCS Weatherization	\$	100,000
Energy Trust of Oregon	\$	65,000
Enterprise charrette grant	\$	4,000
<b>Total additional Sources</b>	<b>\$</b>	<b>1,229,000</b>

Analysis courtesy of  
Housing Development Center



# **Would We Do It Again?**



# Orchards at Orenco Phase II

REACH COMMUNITY DEVELOPMENT



ANKROM MOISAN ARCHITECTS



WALSH CONSTRUCTION CO.

# Innovation Towards Replication

- Best Overall Project and Best Affordable Project, 2015, PHIUS
- Sustainable Project of the Year, 2015, Portland Business Journal
- Golden Hammer Award for Best Project, 2015, Oregon Opportunity Network
- Energy Efficiency Project of the Year & People's Choice Award, 2016, Daily Journal of Commerce
- Best Green Project, 2016, Affordable Housing Finance Magazine's Reader's Choice Award
- Featured in Dwell, Portland Monthly, Politico, Alaska Airlines' in-flight magazine, and local newspapers





# Orchards Phase I vs. Phase II

## Phase I

### (PHIUS+ Certified)


- Innovate to meet REACH strategic goal of building Passive House
- REACH brought significant private investment for this innovation

## Phase II

### (Passive House Inspired)


- Reduce costs to meet OHCS cost containment limits
- Additional private resources not available
- Take lessons learned & best practices from Phase I

# Design Response to Cost Containment




## Phase II (original design)

- L-shaped building with 46 parking stalls
- 57 units in 57,750 SF
- Shallow units to increase daylight
- Community room, office



## Phase II (after design revisions)

- Bar building with 77 parking stalls
- 58 units in 49,900 SF
- Deeper, narrower units
- Reduced number of balconies
- Reduced amenity space




# First Floor Plan




Narrow and Deep...

Wide and Shallow...



CORRIDOR

**Phase I Typ. 1 BR**



CORRIDOR

**Phase II Typ. 1 BR**


# Orchards Phase I & II

## Phase I (PHIUS+ Certified)

- Envelope
  - Fully insulated slab & footings
  - 2x10 walls with 1 ½" exterior insulation
  - Triple-glazed windows
  - Low-slope roof with R-81 insulation
- Whole building ERV with heat pump
- Spaces outside conditioned envelope = very expensive doors & detailing
- Ultra airtight: 0.13 ACH50
- Extended sequencing / duration

## Phase II (pursuing PHIUS+ Certification)



- Envelope
  - Insulated slab. No insulation under footings
  - 2x8 walls with 1" exterior insulation
  - Triple-glazed windows
  - Steep-slope roof with R-60 insulation
  - Vented attic
- Reduced vertical envelope area
  - 35,000 SF → 27,700 SF
- Same HVAC as Phase I, but with better zoning due to orientation of building
- All spaces inside conditioned envelope



**Phase I – Areas  
Outside PH Envelope**

**Phase II – All Areas  
Inside PH Envelope**







## Phase I Foundation

## Phase II Foundation

1 ½" Exterior Insulation  
2 x 10 Wall Framing




1" Exterior Insulation  
2 x 8 Wall Framing




**Phase I Ext. Wall**

**Phase II Ext. Wall**



# Phase I Building Section





## Phase II Building Section























# Phase II - Performance

- Modeled Performance: EUI = 22.2



# Phase II - Lessons Learned

- Airtightness
  - A major challenge at steep slope roof with vented attic...
- Cost premium to achieve Passive House certification can be effectively reduced through more inherently efficient design
- Construction cost: \$173/SF, \$147k/unit)
  - 8% cost/unit reduction from Phase I
  - 15%+ cost reduction if factoring in market escalation...

# Passive Measures - Incremental Costs

- Foundation insulation
- Wall framing
- Exterior insulation at cladding
- Triple-glazed windows (if required)
- Heat recovery at ventilation system
- Materials and labor to achieve airtightness
- Traction elevator
- Certification
- Quality assurance / verification

# Orchards Phase I & II - Costs

## Phase I (PHIUS+ Certified)

- TDC of \$14.5M
- \$255K/unit
- Construction cost: \$9,093,040
- \$158/SF
- \$159,527/unit
- Energy performance:
  - 5 energy models
  - 31-71% better than code

## Phase II (PHIUS+ Certified)

- TDC of \$13.6M
- \$234K/unit
- Construction cost: \$8,531,624
- \$173/SF
- \$147,097/unit
- Energy performance:
  - 3 energy models
  - 29-67% better than code



# Orchards Phase I & II - Costs

## Phase I (PHIUS+ Certified)

- TDC of \$14.5M
- \$255K/unit
- Construction cost: \$9,093,040
- \$158/SF
- \$159,527/unit
- Energy performance:
  - 5 energy models
  - 31-71% better than code
  - Actual data available now

## Phase II (pursuing PHIUS+ Certification)

- TDC of \$13.6M
- \$234K/unit
- Construction cost: \$8,531,624
- \$173/SF
- \$147,097/unit
- Energy performance:
  - 3 energy models
  - 29-67% better than code
  - Actual data available in 2017

# Orchards at Orenco - Proof of Concept

- When implemented with knowledge and skill, passive building measures are cost effective AND provide substantial benefits:
  - Enhanced comfort, health and durability
  - Energy use reduction, leading to operational cost savings
- Orchards at Orenco demonstrates that passive building measures can be implemented at multifamily housing for little additional first cost
- **Life cycle cost & quality benefits likely to far exceed the additional investment at project inception**



ORCHARDS AT ORENCO, PHASE I



ORCHARDS AT ORENCO, PHASE II



# More Information & Insights

- REACH Community Development:
  - [http://reachcdc.org/main/docs/housing\\_development/Orchards\\_PH\\_Case\\_Study.pdf](http://reachcdc.org/main/docs/housing_development/Orchards_PH_Case_Study.pdf)
  - [http://reachcdc.org/main/docs/housing\\_development/Orchards\\_at\\_Orenco\\_I\\_Development\\_Profile\\_update\\_Aug\\_2015.pdf](http://reachcdc.org/main/docs/housing_development/Orchards_at_Orenco_I_Development_Profile_update_Aug_2015.pdf)
- Housing Development Center:
  - <http://www.housingdevelopmentcenter.org/our-work/buildings/orchards-at-orengo/>
- Ankrom Moisan Architects:
  - <https://www.youtube.com/watch?v=ewJUCWI6dqM>
- PHIUS Case Study:
  - <http://www.phius.org/phius-certification-for-buildings-and-products/case-studies/orchards-at-orengo-phase-i>
- BEST 4 Conference Paper:
  - <http://walshconstructionco.com/2015/04/walsh-presents-at-best-4-building-enclosure-science-and-technology-conference/>
- Guest Blog on Green Building Advisor:
  - <http://www.greenbuildingadvisor.com/blogs/dept/guest-blogs/largest-passivhaus-building-us>

# Q & A

**Michael Bonn**  
**Ankrom Moisan Architects**  
**[michaelb@ankrommoisan.com](mailto:michaelb@ankrommoisan.com)**

*This concludes The American Institute of Architects Continuing Education Systems Course*